

TO: STATE CORPORATION COMMISSION
 CONSERVATION DIVISION - PLUGGING
 200 COLORADO DERBY BUILDING
 WICHITA, KANSAS 67202

API number: 15-181-20,087 00-00

C NE NE /4 SEC. 02, 06 S, 37 W
4620 feet from S section line
660 feet from E section line

Operator license# 4767 Lease Jarvis-Stivers well # 1
 Operator: Ritchie Exploration, Inc. County Sherman

Address: 125 N. Market Well total depth 4960 feet *161.20*
Suite 1000 Conductor Pipe: 0 inch @ 0 feet
Wichita, Kansas 67202 Surface pipe 8 5/8 Inch @ 410 feet

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Kelso Casing Pulling License# 6050

Address: Chase, Kansas 67524

Company to plug at: Hour: P.M. Day: 23 Month: June Year: 93

Plugging proposal received from: Dave

Company: Kelso Casing Pulling Phone:

Were: Order 225 sx. 65/35 pozmix - 10% gel. - Allied Cement Company.
Common cement and sand.

Plugging Proposal Received by: Carl Goodrow
 Plugging operations attended by dgent? All[X], Part[], None[]

Completed: Hour: 2:00P.M., Day: 23, Month: June, Year: 93

Actual plugging report: 8 5/8" set @ 410' w/cwc. 300 sx. 4 1/2" set @
4680' w/275 sx. PBTD 4680'. Perf. 4470' - 4614'. Sand back to 4420' with
4 sx. common cement on sand with bailer. Shot @ 3125' anyh. Pipe tight.
Shot @ 2175'. Pipe tight. Displaced 85 sx. cement blend w/150# hulls
mixed in to Max. P.S.I. 600# to 1850'. Shot off @ 1800'. Laid down skid
and rack. Mixed and pumped 85 sx. cement blend to 1850'. Pulled 4 1/2"
to 300' circulated cement into cellar. Laid down 4 1/2" topped of 8 5/8"
with cement slurry. Plug complete.

Remarks:
 Condition of casing(in hole): GOOD BAD Anyh. plug: YES NO
 Bottom plug(in place): YES , CALC , NO Dakota plug: YES , NO
 Plugged through TUBING , CASING . Elevation: GL

I did [X] / did not [] observe the plugging. Carl Goodrow
 RECEIVED STATE CORPORATION COMMISSION

INVOICED
 DATE AUG 03 1993
 INV. NO. 28236

AUG - 2 1993 DM (agent)
8-2-93
 Form CP-2/3