

15-181-20198-00-00

6 030346

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-153-20,330 NW, SEC. 1, T. 6 S, R. 37 WE

4950 feet from W/S section line  
4290 feet from WE section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6978

Lease Name TOVREA Well # B-2

Operator: NIELSON ENTERPRISES INC.

County SHERMAN 156.49

Name & Address 1675 BROADWAY STE. 2770

Well Total Depth 4815 feet

DENVER COLORADO

Conductor Pipe: Size \_\_\_\_\_ feet

80202

Surface Casing: Size 8 5/8 feet 340'

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor HALLIBURTON CEM License Number \_\_\_\_\_

Address OBERLIN KANSAS

Company to plug at: Hour: AM Day: 14 Month: 11 Year: 19 84

Plugging proposal received from GIB SPERLING

(company name) NIELSON ENT. INC. (phone) \_\_\_\_\_

were: SAND ON TOP PBD TO 4580 WITH 4SX.COM.CEM. ON TOP WITH DUMP BAINER SHOOT OF PIPE AND RECOVER.

CALL BACK FOR TOP PLUG WHEN READY TO PLUG.

RECOVERED 1880' OF 4 1/2 CASING. WITH SHOT AT 3110 AT ANHYDRITE ORDER 170 SX. 50/60 P2 6 PPF 3 ACC - 50 SX. GEL - 8 5/8 WIPER PLUG. FOR TOP PLUG.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 11:25AM Day: 14 Month: 11 Year: 19 84

ACTUAL PLUGGING REPORT BOTTOM SAND TO 4580 WITH 4SX.COM.CEM. ON TOP - PIPE SHOT AT 3110' AND 1880' WITH 1880' OF 4 1/2 RECOVERED - TOP PLUG PUMPED DOWN 8 5/8 WITH - 10 SX. GEL + 4 SX. HULLS - 100 SX. CEM. MIX - 40 SX. GEL - 8 5/8 WIPER PLUG. 70 SX. CEM. MIX. - MAX 400# SHOT IN 200# PLUG DOWN AT 11:25AM 11-14-84

RECEIVED STATE CORPORATION COMMISSION

DEC 03 1984

12-3-84

Remarks: \_\_\_\_\_  
(If additional description is necessary, use BACK of this form.)

INVOICED did not observe this plugging.

Signed Carl Goodrow (TECHNICIAN)

DATE 12-12-84

INV. NO. 5914

11-30-84 7