

6

15-181-20036-00-00

030347

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-181-20,036 R
NE, SEC. 1, T. 6 S, R. 37 W E

TECHNICIAN'S PLUGGING REPORT

400 feet from N/E section line
400 feet from W/E section line

Operator License # 16978

Lease Name RALPH BROWN Well # 1

Operator: NIELSON ENTERPRISES INC.
Name & Address 1675 BROADWAY STE. 2770
DENVER COLORADO
80202

County SHERMAN 154.38
Well Total Depth 4750 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 332

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor HALLIBURTON SERVICES License Number _____

Address OBERLIN KANSAS

Company to plug at: Hour: AM Day: 14 Month: 11 Year: 19 84

Plugging proposal received from GIB SPERLING

(company name) NIELSON ENTERPRISES INC. (phone) _____

were: DUMP SAND ON PBTD TO 4600 WITH 4SX.COM.CEM. ON TOP WITH BAIER
SHOOT AND RECOVER 4 1/2 CASING.

SHOTS AT 3110' ANHY 1800' AND 1300' - WITH 1500' OF 4 1/2" CASING RECOVERED
ORDER 170 SX. 50SX. 67 GEL 3 1/2" - 50SX. GEL - 4SX. HULLS FOR TOP PLUG

CALL BACK WHEN READY FOR TOP PLUG

Plugging Proposal Received by Carl Goodnow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 9:45AM Day: 14 Month: 11 Year: 19 84

ACTUAL PLUGGING REPORT DUMPED SAND TO 4600' WITH 4SX.COM.CEM. ON TOP

TOP PLUG - PUMPED DOWN 8 5/8" WITH - 10SX. GEL - 4SX. HULLS - 100SX. CEM. MIX

40SX. GEL. - 8 5/8" WIPER PLUG - 70SX. CEM. MIX - MAX. 400# SHUT IN 150'

PLUG DOWN AT 9:45AM 11-14-84

RECEIVED
STATE CORPORATION COMMISSION
DEC 03 1984
CONSERVATION DIVISION
Wichita, Kansas
12-3-84

Remarks: (If additional description is necessary, use BACK of this form.)

(If you did not observe this plugging.)

INVOICED
DATE 12-12-84
INV. NO. 5912

Signed Carl Goodnow (TECHNICIAN)

FORM CP-2/3 Rev. 01-84
11-30-84
8