

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 163-22,026 -00-00

NE, Sec. 13, T 7 S, R 20 W/E

1480 feet from N section line

990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6691

Lease Name STICE Well # 4-13

Operator: TERRA-MAX ENERGY,  
Name & INC.  
Address BOX 848  
MONUMENT, CO  
80132

County ROOFS.

Well Total Depth 3552 feet \$115.44

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 200

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor CIRCLE M. DRILLING License Number 6591 TAG 851

Address BOX 128 OBERLIN, KANS. 67749

Company to plug at: Hour: 6:00 AM Day: 3<sup>RD</sup> Month: MAY Year: 19 83

VERBAL PLUGGING ORDERS GIVEN TO GENE OWEN

(company name) CIRCLE M. DRILLING (phone) 303-488-2804

were: 8 5/8" 200 ELSB. CUL #150<sup>ST</sup> 60<sup>ST</sup> 1/40 FORMIX. 2% GEL. 3% CA-CL. (SUN CNT)

ORDER 210<sup>ST</sup> 50<sup>ST</sup> 1/50 FORMIX 6% GEL-3% CA-CL. AND 8 5/8" PLUG

SPOT WITH DRILL STEM - WITH HEAVY MUD BETWEEN ALL PLUGS.

ELV. 2036 G.L. ANNY. 1587<sup>EL</sup>, PENETRATED ARBUCKLE

@ 3506<sup>EL</sup>.

Signed Morgan Schmidt  
(TECHNICIAN) 801C

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 6:30 AM Day: 3<sup>RD</sup> Month: MAY Year: 19 83

ACTUAL PLUGGING REPORT

ORDERED 210<sup>ST</sup> 50<sup>ST</sup> 1/50 FORMIX 6% GEL-3% CA-CL. AND 8 5/8" PLUG.

SPOTTED WITH DRILL STEM - WITH HEAVY MUD BETWEEN ALL PLUGS.

1<sup>ST</sup> PLUG @ 3480<sup>EL</sup> #1/20<sup>ST</sup> CNT. 2<sup>ND</sup> PLUG @ 1590<sup>EL</sup> #1/20<sup>ST</sup> CNT.

3<sup>RD</sup> PLUG @ 960<sup>EL</sup> #1/100<sup>ST</sup> CNT. 4<sup>TH</sup> PLUG @ 240<sup>EL</sup> #1/40<sup>ST</sup> CNT.

5<sup>TH</sup> PLUG <sup>SOLID BRIDGE</sup> HULL'S - PLUG @ 40<sup>EL</sup> #1/10<sup>ST</sup> CNT, 10<sup>ST</sup> IN RAT HOLE (CIRCULATE)

Remarks: 10<sup>ST</sup> IN RAT HOLE (CIRCULATE) CEMENTED BY SUN CNT.

I hereby certify that the above plugging instructions were given as herein stated and that I  / did not) observe this plugging.

Signed Morgan Schmidt  
(TECHNICIAN) 801C

RECEIVED  
STATE CORPORATION COMMISSION

FORM CP-2/3  
Rev. 9-82

INVOICED MAY 06 1983  
DATE 5-13-83 MAY 06 1983  
CONSERVATION DIVISION  
Wichita, Kansas  
INV. NO. 4303-W