

15-181-05043-00-01

4-032391

D-07,054

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15- -

C SE NW /4 SEC. 10, 06, 37 W
3300 feet from S section line
3300 feet from E section line

Operator license# 5099
Operator: J-W Operating Company
Address: P.O. Box 305
Wray, Colorado 80758

10/26

Lease: Llanos Well # 5
County: Sherman
Well total depth 5003 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 9 5/8 Inch @ 375 feet

Aband. oil well___, Gas well___, Input well___, SWD_X___, D & A___

Plugging contractor: J-W Operating Company License# 5099

Address: P.O. Box 305 - Wray, Colorado 80758

Company to plug at: Hour: A.M. Day: 26 Month: October Year: 1999

Plugging proposal received from: Ray Bivens

Company: J-W Operating Company Phone: _____

Were: Order 350 sxs 60/40 pozmix - 10% gel - 500# hulls - 30 sxs gel.
Order work string.
Allied Cement Company.

Plugging Proposal Received by: Carl Goodrow
Plugging operations attended by agent? All[], Part[X], None[]

Completed: Hour: A.M., Day: 26 Month: October, Year: 1999

Actual plugging report: 9 5/8" set at 375' w/330 sxs cwc. 7" set at 4949' w/105 sxs.
OH. 4956' - 5003'. Top stage at 2300' to 1700'. Spotted with tubing - 50 sxs cement blend
with 300# hulls to bottom with gel spacer to 2400' w/50 sxs cement blend with 200# hulls
mixed in to 1700'. Shot off casing at 1700'. Pulled to 450' and circulated cement to
surface with 135 sxs. Plug complete.

Remarks: _____
Condition of casing(in hole): GOOD___ BAD___ Any plug: YES X NO___
Bottom plug(in place): YES___, CALC___, NO___ Dakota plug: YES X, NO___
Plugged through TUBING___, CASING___ Elevation: _____ GL

I did[X] / did not[] observe the plugging.

Carl Goodrow
(agent)

INVOICED
DATE 12/6/99
INV. NO. 60917

100

RECEIVED
STATE CORPORATION COMMISSION
NOV 18 1999
CONSERVATION DIVISION
Wichita Kansas

Form CP-2/3