

3 022901

To:

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

130 S. Market, Room 2078  
Wichita, Kansas 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 101

Operator: STATE OF KANSAS FeeFund

Name & \_\_\_\_\_

Address \_\_\_\_\_

AB oil well \_\_\_\_\_ Gas Well \_\_\_\_\_ SWD Well/ Input Well E-25,284 D & A \_\_\_\_\_

Other well as hereinafter indicated: \_\_\_\_\_

Plugging Contractor: KEPLEY WELL SERVICE, LLC Lic. # 30670

Address: 19245 FORD ROAD, CHANUTE, KANSAS 66720

Company to plug at: Hour: 8:00A.M. Day: \_\_\_\_\_ Month: 28 2005

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300

Were: THIS WELL CONSISTED OF 2 7/8" CASING TO 830' THAT HAD  
BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TO  
CIRCUALATE THE 2 7/8" CASING FULL OF CEMENT.

**RECEIVED**  
**OCT 24 2005**

**KCC WICHITA**

Plugging Proposal Received by: CLAYTON P. TITEL

Plugging attended by Agent: All \_\_\_\_\_ Part \_\_\_\_\_ Technician None \_\_\_\_\_ X

Operations Completed: Hour: 10:00A.M. Day: \_\_\_\_\_ Month: 28 2005

Actual Plugging Report: 1" PIPE WAS RAN INTO THE 2 7/8" CASING TO 825'.

CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE  
2 7/8" CASING AT SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT WAS  
FILLED FROM SURFACE. 45 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

Remarks: ( GPS SESSION PT. NO.20 ) ( WELL NO. 5-API NO. 15-001-28,177 )

(If additional description is necessary, use BACK of this form.)

I DID NOT observe this plugging.

Signed:

Clayton P. Titel  
TECHNICIAN

*Keep  
BEM  
11-1-05  
Per Footages*

API NUMBER SE,SE,NE,NE 1/4

15-001-28177-00-01  
CONTROL NO. 20060001-014

Sec/Twp/Rge S24-T.26S.-R.17E.

4173 feet from south section line

225 feet from east section line

Lease/Well# HAROLD WOLF NO. 5

County ALLEN

Well Total Depth 830' feet

Production Pipe: 2 7/8" Size Feet 830'

Surface Casing: 5" Size Feet 30'

*KCC  
BEM  
11-01-05  
REBDM  
Intent*

*B*