

3 022904

To:

STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER 15-001-28249-00-01
CONTROL NO. 20060001-024
SW,SE,NE 1/4 Sec/Twp/Rge S24-T.26S.-R.17E.

2853 feet from south section line
892 feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # LO1
Operator: STATE OF KANSAS Fee Fund

Lease/Well# HAROLD WOLF NO.I-10
County ALLEN

Name & _____

Well Total Depth 831' feet

Address _____

Production Pipe: 2 7/8" Size Feet 831'

AB oil well _____ Gas Well _____ SWD Well/ Input Well E-25,284 D & A _____

Surface Casing: 7" Size Feet 28'

Other well as hereinafter indicated: _____

Plugging Contractor: KEPLEY WELL SERVICE, LLC Lic. # 30670

Address: 19245 FORD ROAD, CHANUTE, KANSAS 66720

Company to plug at: Hour: 10:00A.M. Day: _____ Month: 28 2005

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300

Were: THIS WELL CONSISTED OF 2 7/8" CASING TO APPROXIMATELY 831' THAT

HAD BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS
TO CIRCULATE THE 2 7/8" CASING FULL OF CEMENT.

RECEIVED

OCT 24 2005

KCC WICHITA

Plugging Proposal Received by: CLAYTON P. TITEL

Plugging attended by Agent: All _____ Part _____
TECHNICIAN
None X

Operations Completed: Hour: 12:00P.M. Day: _____ Month: 28 2005

Actual Plugging Report: 1" PIPE WAS RAN INTO THE 2 7/8" CASING TO 810'

CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE
2 7/8" CASING AT SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT WAS
FILLED FROM SURFACE. 37 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

Remarks: (GPS SESSION PT. NO.32) (WELL NO.I-10. API NO.15-001-28,249)
(If additional description is necessary, use BACK of this form.)

I DID NOT observe this plugging.

Signed:

Clayton P. Titel
TECHNICIAN