

6 030453 15-181-20218-0000

R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-

NENE NW SEC. 13, T 6 S, R 37 W/D

4950 feet from N(S) section line

2970 feet from W(E) section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5364

Lease Name LYMAN Well # 1

Operator: BEREN CORP.

County SHERMAN 161.85

Name & Address 970 4th FINANCIAL CTR

Well Total Depth 4980 feet

WICHITA, KANSAS

Conductor Pipe: Size feet

67202

Surface Casing: Size 8 5/8 feet 362'

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor KELSO CASING PULLING License Number 6050

Address CHASE, KANSAS 67524

Company to plug at: Hour: AM Day: 24 Month: 5 Year: 19 85

Plugging proposal received from RONNIE

(company name) KELSO CASING (phone)

were: 8 5/8 SET @ 362' w/ 300 SX. 4 1/2 SET @ 4979 w/ 275 SX. PERF' 4870-71 4490-91
4468-71 Order Sand 45X. COM. CEM. FOR BOTTOM PLUG OFF, SHOOT PIPE, AND STRIP.
ORDER 180 SX. 50/50 POZ 6% GEL 3% CC 40 SX. GEL 8 5/8 W.P. 4 SX. HULLS SUN CEM.
WELLBROCK WATER TRUCKS

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 11: AM Day: 24 Month: 5 Year: 19 85

ACTUAL PLUGGING REPORT BOTTOM SAND ON PBD @ 4485 TO 4400 w/ 4 SX. COM. CEM. ON SAND
w/ BAILER, TOP PLUG - PUMP DOWN 8 5/8 w/ 4 SX. HULLS 6 SX. GEL. 100 SX. CEM. MIX.
34 SX. GEL. 8 5/8 W.P. 80 SX. CEM. MIX. MAX. PSI. 400# GHOSE IN 200# PLUG.
COMPLETE. STRIPPED 2200' OF 4 1/2" CASING.

RECEIVED STATE CORPORATION COMMISSION JUN 05 1985 6-5-85

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

DATE 6-0-85

Signed Carl Goodrow (TECHNICIAN)

INV. NO. 8409