

3 022868

15-001-27803-00-00

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER CONTROL NO. 20050053-044
NE,NW,NW 1/4 Sec/Twp/Rge S.19-T.26S.-R.18E.
5089 feet from south section line
4119 feet from east section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 101
Operator: STATE OF KANSAS Fee Fund
Name & FEE FUND PLUGGING
Address _____
AB oil well X Gas Well _____ SWD Well/ Input Well _____

Lease/Well# KENNITH WOLF NO10
County ALLEN
Well Total Depth 800' feet
Production Pipe: 2 7/8" Size Feet 800'
Surface Casing: 6 5/8" Size Feet 20'
D & A _____

Other well as hereinafter indicated: _____

Plugging Contractor: KEPLEY WELL SERVICE,LLC Lic. # 30670
Address: 19245 FORD ROAD, CHANUTE, KANSAS 66720

Company to plug at: Hour: 11:00A.M. Day: _____ 8 Month: 9 2005

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300

Were: THIS WELL CONSISTED OF 2 7/8" CASING TO APPROXIMATELY 800' THAT
HAD BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS
TO SQUEEZE THE 2 7/8" CASING FULL OF CEMENT FROM SURFACE.

Plugging Proposal Received by: CLAYTON P. TITEL

Plugging attended by Agent: All _____ Part _____
TECHNICIAN
None X

Operations Completed: Hour: 12:00P.M. Day: _____ 8 Month: 9 2005

Actual Plugging Report: THE PUMP TRUCK WAS CONNECTED DIRECTLY TO
THE 2 7/8" CASING. COTTON SEED HULLS WERE MIXED WITH THE FIRST OF THE
CEMENT TO BE PUMPED. CEMENT WAS PUMPED INTO THE 2 7/8" CASING UNTIL
THE WELL WOULD HOLD PRESSURE. THE WELL WAS THEN SHUT IN AT 750PSI.
33 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

Remarks: (GPS SESSION PT. NO.11) (API NO.15-001-27,803. FOR WELL NO.11)
(If additional description is necessary, use BACK of this form.)

I DID NOT observe this plugging.

Signed: Clayton P. Titel
TECHNICIAN

RECEIVED
SEP 21 2005
KCC WICHITA

Bm