

3 022866

15-001-28070-0001

To:

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

130 S. Market, Room 2078

Wichita, Kansas 67202

KCC  
BEM  
11-1-05 GPS  
RBDMS  
Per Footages  
SE  
SW, SW, NW 1/4

API NUMBER CONTROL NO. 20050053-034

Sec/Twp/Rge S.19-T.26S.-R.18E.

2801 feet from south section line

4248 feet from east section line

TECHNICIAN'S PLUGGING REPORT

Lease/Well# FORD NO.1

Operator License # 101

County ALLEN

Operator: STATE OF KANSAS Fee Fund

Well Total Depth 808' feet

Name & FEE FUND PLUGGING

Production Pipe: 2 7/8" Size Feet 808'

Address

Surface Casing: 6 5/8" Size Feet 30'

AB oil well \_\_\_\_\_ Gas Well \_\_\_\_\_ SWD Well/ Input Well E-26,001 D & A \_\_\_\_\_

Other well as hereinafter indicated:

Plugging Contractor: KEPLEY WELL SERVICE, LLC Lic. # 30670

Address: 19245 FORD ROAD, CHANUTE, KANSAS 66720

Company to plug at: Hour: 8:00A.M. Day: \_\_\_\_\_ 8 Month: 9 2005

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300

Were: THIS WELL CONSISTED OF 2 7/8" CASING TO 808' THAT

HAD BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS

TO SQUEEZE THE 2 7/8" CASING FULL OF CEMENT FROM SURFACE.

Plugging Proposal Received by: CLAYTON P. TITEL

Plugging attended by Agent: All \_\_\_\_\_ Part \_\_\_\_\_ TECHNICIAN None X

Operations Completed: Hour: 10:00P.M. Day: \_\_\_\_\_ 8 Month: 9 2005

Actual Plugging Report: THE PUMP TRUCK WAS CONNECTED DIRECTLY TO

THE 2 7/8" CASING. COTTON SEED HULLS WERE MIXED WITH THE FIRST OF THE

CEMENT TO BE PUMPED. CEMENT WAS PUMPED INTO THE 2 7/8" CASING UNTIL

THE WELL WOULD HOLD PRESSURE. THE WELL WAS THEN SHUT IN AT 800PSI.

35 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

Remarks: (GPS SESSION PT. NO.34) (API NO.15-001-28,070. FOR WELL NO.1)

(if additional description is necessary, use BACK of this form.)

I DID NOT observe this plugging.

RECEIVED  
SEP 21 2005  
KCC WICHITA

Signed:

Clayton P. Titel  
TECHNICIAN

B