

3 022867

*Keep  
BEM  
11-1-05  
Per Footages - GPS  
SW SE*

15-001-28071-00-00

To:

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

130 S. Market, Room 2078

Wichita, Kansas 67202

API NUMBER CONTROL NO. 20050053-035  
SW,SW,NW 1/4 Sec/Twp/Rge S.19-T.26S.-R.18E.

2801 feet from south section line

4580 feet from east section line

TECHNICIAN'S PLUGGING REPORT

Lease/Well# FORD NO.2

Operator License # 101

County ALLEN

Operator: STATE OF KANSAS Fee Fund

Well Total Depth 800' feet

Name & FEE FUND PLUGGING

Production Pipe: 2 7/8" Size Feet 800'

Address

Surface Casing: 6 5/8" Size Feet 20'

AB oil well X Gas Well SWD Well/ Input Well D & A

Other well as hereinafter indicated:

Plugging Contractor: KEPLEY WELL SERVICE,LLC Lic. # 30670

Address: 19245 FORD ROAD, CHANUTE, KANSAS 66720

Company to plug at: Hour: 10:00A.M. Day: 8 Month: 9 2005

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300

Were: THIS WELL CONSISTED OF 2 7/8" CASING TO APPROXIMATELY 800' THAT HAD BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TO SQUEEZE THE 2 7/8" CASING FULL OF CEMENT FROM SURFACE.

Plugging Proposal Received by: CLAYTON P. TITEL

Plugging attended by Agent: All Part Technician None X

Operations Completed: Hour: 11:00P.M. Day: 8 Month: 9 2005

Actual Plugging Report: THE PUMP TRUCK WAS CONNECTED DIRECTLY TO THE 2 7/8" CASING. COTTON SEED HULLS WERE MIXED WITH THE FIRST OF THE CEMENT TO BE PUMPED. CEMENT WAS PUMPED INTO THE 2 7/8" CASING UNTIL THE WELL WOULD HOLD PRESSURE. THE WELL WAS THEN SHUT IN AT 1000PSI. 36 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

Remarks: (GPS SESSION PT. NO.35) (API NO.15-001-28,071. FOR WELL NO.2)  
(If additional description is necessary, use BACK of this form.)

I DID NOT observe this plugging.

Signed:

*Clayton P. Titel*  
TECHNICIAN

RECEIVED  
SEP 21 2005  
KCC WICHITA

*Bum*