

4-032265

10-21

API Number: 15-181-20,297-00-00

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

150' W. of  
SW NE NW /4 SEC. 21, 06, 37 W  
4290 feet from S section line  
3780 feet from E section line

Operator license# 9482

Lease: Query Well # 1

Operator: National Petroleum Reserves

County: Sherman 158.02

Address: 250 N. Rock Road - #130  
Wichita, Kansas 67206

Well total depth 4862 feet  
Conductor Pipe: 0 inch @ 0 feet  
Surface pipe 8 5/8 Inch @ 362 feet

Aband. oil well X, Gas well, Input well, SWD, D & A

Plugging contractor: Mike's Testing & Salvage License# 3307

Address: Chase, Kansas 67525

Company to plug at: Hour: A.M. Day: 21 Month: October Year: 1997

Plugging proposal received from: James Ray

Company: Mike's Testing & Salvage Phone: -

Were: Order 240 sxs 60/40 pozmix - 10% gel - 400# hulls.  
Order sand and common cement.

Plugging Proposal Received by: Carl Goodrow  
Plugging operations attended by agent? All [ X ], Part [ ], None [ ] 11-3-97

Completed: Hour: 11:15 A.M., Day: 21 Month: October Year: 1997

Actual plugging report: 8 5/8" set at 362' w/245 sxs cwc. 4 1/2" set at 4861' w/165 sxs.  
Prod. Perfs 4684' - 4688'. TDC 4201'. Sanded back to 4590' w/4 sxs common cement on sand  
with bailer. Shots 3400' - 3000' - 2600' and free at 2280'. Mixed and pumped down 4 1/2"  
150 sxs cement blend. Pulled casing to 350'. Mixed and pumped 50 sxs cement blend. Pulled  
casing. Pumped down 8 5/8" w/40 sxs cement blend. Cement top fell to 144'. Used all of the  
material. Operator will top off later.

Remarks:  
Condition of casing(in hole): GOOD BAD Anhy.plug: YES X NO  
Bottom plug(in place): YES, CALC, NO Dakota plug: YES X, NO  
Plugged through TUBING, CASING. Elevation: GL

I [ X ] did not [ ] observe the plugging.

INVOICED

Carl Goodrow  
(agent)

DATE 11-4-97  
INV. NO. 49425