

3-31

4-050305

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-181-20,292 00-00

N2 SW NW /4 SEC. 21, 06 S, 37 W
3630 feet from S section line
4620 feet from E section line

Operator license# 5316

Lease: Query Well # 1

Operator: Falcon Exploration, Inc.

County: Sherman 164.13

Address: P.O. Box 75067
Wichita, Kansas 67275-5067
316-262-1378

Well total depth 5050 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 392 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Plains Well Service License# -

Address: Ness City, Kansas 67560

Company to plug at: Hour: P.M. Day: 31 Month: March Year: 1998

Plugging proposal received from: Bill Hammack

Company: Falcon Exploration, Inc. Phone: 316-262-1378

Were: Order 60/40 pozmix - 10% gel and 500# hulls.
8 5/8" set at 392' w/250 sxs. 4 1/2" set at 5049' w/250 sxs.
Perfs 4696' - 4700'. Anhydrite 3098' - 3112'.

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All , Part , None]

Completed: Hour 3:00 P.M. Day: 31, Month: March, Year: 1998

Actual plugging report: Perf Tech set CIBP at 4625' and shot 4 1/2" casing at 2012'.
Pulled 4 1/2" to 1927' - pumped 100 sxs cement and 400# hulls. Pulled 4 1/2" casing to 460'
and pumped 40 sxs cement and 100# hulls. Pulled 4 1/2" casing to 150' and pumped 60 sxs
cement to circulate. Pulled rest of 4 1/2" casing and topped off with 5 sxs cement.

Remarks:

Condition of casing(in hole): GOOD BAD Anhy.plug: YES NO
Bottom plug(in place): YES , CALC , NO Dakota plug: YES , NO
Plugged through TUBING , CASING Elevation: 3449 GL

I did / did not observe the plugging.

Maurin Miller
(agent)

Form CP-2/3

INVOICED

DATE 4-8-98

INV. NO. 50337

3-31 JUN 17 1998

42-98