

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
130 S. Market - Room 2078  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

15-081-20599-00-00  
~~20599~~

API NUMBER 15-067-20810-0000

LEASE NAME ROY

WELL NUMBER 13-20

1250' FSL Ft. from S Section Line

1250' FEL Ft. from E Section Line

SEC. 20 TWP. 29S RGE. 34W (E) or (W)

COUNTY HASKELL

Date Well Completed 4/29/90

Plugging Commenced 8/18/05

Plugging Completed 8/18/05

RECEIVED

AUG 31 2005

KCC WICHITA

LEASE OPERATOR PIONEER NATURAL RESOURCES USA, INC.

ADDRESS 5205 N. O'CONNOR BLVD., ROOM 1325 - IRVING, TX 75039

PHONE # (727) 444-9001 OPERATORS LICENSE NO. 4824

Character of Well GAS

(Oil, Gas, O&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 6/20/05 (date)

by DAVID WILLIAMS (KCC District Agent's Name)

is ACO-1 filed? YES If not, is well log attached? \_\_\_\_\_

Producing Formation CHASE Depth to Top 3007' KB Bottom 2854' T.D. 2936'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
CHASE	GAS	2538'	2788'	8 5/8"	644'	0
				5 1/2"	2935'	0'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set

8/18/05 Witnessed by K. Jehlik, KCC. Set CIBP @2450' KB, spot 20' cmt, Revise PBD @2430'. Load hole w/17 bbl 9ppg 36cp mud to 1750' & 15 sx cmt plug frm 1750'-1630' & 23 bbl mud frm 1630'-650' & 70 sx cement plug frm 650' to 0'. NU cmtr to 8 5/8" surf csg & pmp 26 sx cmt from 120'-0'. Cut 8 5/8" surf csg & 5 1/2" prod csg 3" bgl, weld on trash cover-ID plate.


Name of Plugging Contractor SARGENT AND HORTON PLUGGING INC. License No. 31151

Address RT. 1, BOX 49BA TYRONE OK 73951-9731

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: PIONEER NATURAL RESOURCES USA, INC.

STATE OF TEXAS COUNTY OF DALLAS, ss.

LINDA KELLY (Employee of Operator) or (Operator) of above-described well, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.



(Signature) Linda Kelly  
(Address) 5205 N. O'CONNOR BLVD. RM 1325 IRVING TX 75039

AND SWORN TO before me this 29th day of August, 20 05  
My Commission Expires: 7/14/2009 Notary Public

*Bm*