

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

RECEIVED

OCT 19 2005

Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

KCC WICHITA

Lease Operator: American Warrior INC

Address: P.O. box 399, Garden City, Ks 67846

Phone: (620) 275-2963 Operator License #: 4058

Type of Well: oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: 9-14-05 (Date)

by: Virgil Clothier (KCC District Agent's Name)

Is ACO-1 filed? Yes No If not, is well log attached? Yes No

Producing Formation(s): List All (If needed attach another sheet)

Arbuckle Depth to Top: 3214 Bottom: 3218-1/2 T.D. 3218-1/2
Depth to Top: _____ Bottom: _____ T.D. _____
Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-159-01667-00-00

Lease Name: Vokland-Vokland WF

Well Number: #9-B

Spot Location (QQQQ): C - E/2 - SE - NW

3300' Feet from North / South Section Line

2970 Feet from East / West Section Line

Sec. 5 Twp. 18 S. R. 10 East West

County: Rice

Date Well Completed: 3-14-1940

Plugging Commenced: 9-21-05

Plugging Completed: 9-23-05

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
	Surface Pipe	203	surface	8-5/8"	203	none
	Production Csg.	3214	surface	5-1/2"	3214	None

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Perf @ 1260', 860', 260', ran 2-3/8" tbg, 1st plug, 25sks @ 2700', 2nd plug @ 35 sks 1260', 3rd plug @ 35 sks 860', 4th plug @ 260' pump, 70 sks cem, cem cir. hook up to 5-1/2" pump 10 sks, SI w/ 100#s, (Cement 60/40 poz 4% gel) top off 5-1/2" w/ 15 sks, cut off csg. 6' below GL. Fill cellar.


Name of Plugging Contractor: Swift Servicer INC License #: 32382

Address: P.O. box 466, Ness city, Ks, 67560

Name of Party Responsible for Plugging Fees: American Warrior INC

State of Kansas County, Finney, ss.

Kevin wiles SR/ Production Supt, (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the



(Signature) [Signature]
KEVIN WILES, SR
(Address) Same As Above

SUBSCRIBED and SWORN TO before me this 17th day of OCTOBER, 2005

Erica Kuhlmeier My Commission Expires: 09-12-09
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

[Handwritten mark]