

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

RECEIVED
OCT 19 2005
KCC WICHITA
Form CP-4
December 2003
Type or Print on this Form
Form must be Signed
All blanks must be Filled

Lease Operator: American Warrior INC
Address: P.O. box 399, Garden City, Ks 67846
Phone: (620) 275-2963 Operator License #: 4058
Type of Well: oil Docket #: _____
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)
The plugging proposal was approved on: 9-14-05 (Date)
by: Virgil Clothier (KCC District Agent's Name)
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
Arbuckle Depth to Top: 3225 Bottom: 3230 T.D. 3230

Depth to Top: _____ Bottom: _____ T.D. _____

Depth to Top: _____ Bottom: _____ T.D. _____

API Number: 15-159-01985-00-00
Lease Name: Vokland Volkland
Well Number: # 8
Spot Location (QQQQ): C - NW - Sw - SE
990 Feet from North / South Section Line
2310 Feet from East / West Section Line
Sec. 32 Twp. 18 S. R. 9 East West
County: Rice
Date Well Completed: 10-29-1948
Plugging Commenced: 9-19-05
Plugging Completed: 9-22-05

KCC
66M
10/20/05
RBDMS

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
	Surface Pipe	210'	surface	8-5/8"	210'	none
	Production Csg.	3225'	surface	5-1/2"	3225'	None

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Set CIBP, @ 3200' dump 5 sks cem on top, Per: 1250', 850', & 260', ran 2-3/8" tbg, pump 35 sks. cem @ 1250; pump 35 sks. @ 850; pump, 40 sks cem @ 260 cem cir. pull tbg, hook up to 5-1/2" pump 20 sks cem. cement cir thru surface pipe, close valve, pump 20 sks cem SI w/ 225 #s (Cement 60/40 poz 4% gel) top off 5-1/2" w/ 10 sks, cut off ceg 6' below ground level, fill cellar.

Name of Plugging Contractor: Swift Servicer INC License #: 32382
Address: P.O. box 466, Ness city, Ks, 67560
Name of Party Responsible for Plugging Fees: American Warrior INC
State of Kansas County, Finney, ss.

Kevin wiles SR/ Production Supt, (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.



(Signature) [Signature]
KEVIN WILES SR
(Address) Same As Above

SUBSCRIBED and SWORN TO before me this 17th day of OCTOBER, 2005
Erica Kuhlmeier My Commission Expires: 09-12-09
Notary Public

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

[Handwritten mark]