

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
WELL PLUGGING RECORD  
K.A.R. 82-3-117

RECEIVED

OCT 19 2005

KCC WICHITA

Form CP-4  
December 2003  
Type or Print on this Form  
Form must be Signed  
All blanks must be Filled

Lease Operator: Apollo Energies, Inc.

Address: 10378 N 281 HWY, Pratt Kansas 67124

Phone: (620) 672-9001 Operator License #: 30481

Type of Well: oil and gas Docket #: \_\_\_\_\_  
(Oil, Gas D&A, SWD, ENHR, Water Supply Well, Cathodic, Other) (If SWD or ENHR)

The plugging proposal was approved on: March 2, 2005 (Date)

by: Jim Holland (KCC District Agent's Name)

Is ACO-1 filed?  Yes  No If not, is well log attached?  Yes  No

Producing Formation(s): List All (if needed attach another sheet)

Morrow Sand Depth to Top: 5660 Bottom: 6050 T.D. 6400

Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

Depth to Top: \_\_\_\_\_ Bottom: \_\_\_\_\_ T.D. \_\_\_\_\_

API Number: 15 - 189-21,222 .. 00-00

Lease Name: Pottorf

Well Number: #1 - 31

Spot Location (QQQQ): NW-SW-NE   
 1388 Feet from  North /  South Section Line

2121 Feet from  East /  West Section Line

Sec. 24 Twp. 31 S. R. 37  East  West

County: Stevens

Date Well Completed: July, 1988

Plugging Commenced: October 4, 2005

Plugging Completed: October 5, 2005

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface Conductor & Production)				
Formation	Content	From	To	Size	Put In	Pulled Out
Morrow Sand	oil/gas	0'	1754	8 5/8"	1753	0
Morrow Sand	oil/gas	0'	6400	5 1/2" (14#)	6400	1718

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

Set CIBP at 5600' with 2 sxs cement on top. Load hole with mud, Cut casing at 1711', spot 50 sxs cement from 1711 to 1561,

Pulled to 650', spot 30 sxs cement from 650 to 550', pull to 40', pump 20 sxs cement. Cut off and capped 3' below ground level.

Name of Plugging Contractor: Sargent and Horton Plugging License #: 31151

Address: RR1 Box 49BA, Tyrone, Ok 73951

Name of Party Responsible for Plugging Fees: Apollo Energies, Inc

State of Kansas County, Pratt, ss.

I, Scott Alberg (Employee of Operator) or (Operator) on above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

(Signature) \_\_\_\_\_

(Address) 10378 N. 281 HWY, Pratt, Kansas 67124

SUBSCRIBED and SWORN TO before me this 17 day of October, 2005

Nancy E. Harrel My Commission Expires: December 17, 2006  
Notary Public

**NANCY E. HARREL**  
Notary Public - State of Kansas  
My Appt. Expires 12-17-2006

KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

*[Handwritten signature]*