

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-141-20361-0000

LEASE NAME Joyce Applegate B

RECEIVED

OCT 20 2005

KCC WICHITA

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1

1,060 Ft. from S Section Line

2,130 Ft. from E Section Line

SEC. 28 TWP. 9 RGE. 12 KEXor(W)

COUNTY Osborne

Date Well Completed 10-11-05

Plugging Commenced 10-11-05

Plugging Completed 10-11-05

LEASE OPERATOR Brungardt Oil & Leasing, Inc.

ADDRESS PO Box 87L, Russell, KS 67665

PHONE#(785) 483-4975 OPERATORS LICENSE NO. 3956

Character of Well D & A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 10-11-05 (date)

by Pat Staab (KCC District Agent's Name).

Is ACO-1 filed? No If not, is well log attached? Yes

Producing Formation _____ Depth to Top _____ Bottom T.O. 3,400'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8"	208'	Cmtd. w/160 sax

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from ___ feet to ___ feet each set. Push bridge plug to 906', pump 25 sax cement on plug thru drill pipe. Push bridge plug to 795', pump 100 sax cement on plug thru drill pipe. Push bridge plug to 285', pump 40 sax cement on plug thru drill pipe. Push wiper plug to 40', dump 10 sax cement on plug to cellar. Dump 15 sax cement down rat hole and 10 sax cement down mouse hole.

Name of Plugging Contractor Shields Drilling Co. License No. 5184

Address Shields Bldg., Russell, KS 67665

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Brungardt Oil & Leasing, Inc.

STATE OF KANSAS COUNTY OF RUSSELL, ss.

Jack P. Beeman Contractor
above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed th. the same are true and correct, so help me God.

(Signature) Jack P Beeman

(Address) Shields Bldg., Russell, KS 67665

SUBSCRIBED AND SWORN TO before me this 18th day of October, 2005



My Commission Expires: _____

Ruth Phillips
Notary Public

Bm
Form 07