

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-097-20437-00-00
Spot: S2S2SW Sec/Twnshp/Rge: 35-28S-18W
330 feet from S Section Line, 3960 feet from E Section Line
Lease Name: KELLER Well #: 1
County: KIOWA Total Vertical Depth: 3654 feet

Operator License No.: 8061
Op Name: OIL PRODUCERS INC. OF KANSAS
Address: 1710 WATERFRONT PARKWAY
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	3654	2420	WITH 150 SX CMT
SURF	8.625	425		WITH 300 SX CMT

\$ 118⁷⁶

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 10/25/2005 2:30 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: JOE MAES Company: QUALITY WELL SERVICE, INC. Phone: (620) 786-2001

Proposed Plugging Method: SAND OFF @ 3508' WITH 4 SX CMT. PLUG AT 1200 WITH 2 SX GEL & 40 SX CMT. PLUG AT 450' WITH 50 SX CMT. PLUG AT 20' WITH 10 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/25/2005 4:00 PM KCC Agent: JERRY W. STAPLETON

Actual Plugging Report:

SANDED TO 3508' WITH 4 SX CMT WITH DUMP BAILER. 1ST PLUG AT 1200' WITH 12 SX GEL & 50 SX CMT. 2ND PLUG AT 450' WITH 50 SX CMT. 3RD PLUG AT 35' WITH 10 SX CMT.

Perfs:


Top	Bot	Thru	Comments
3558	3564		

Remarks: USED 60/40 POZMIX 6% GEL BY SERVICE ACID.

Plugged through: CSG

INVOICE
DATE 10-31-05
INV. NO. 2006060689

District: 01



Signed Jerry W. Stapleton PART II
(TECHNICIAN)

RECEIVED
OCT 31 2005
KCC WICHITA

Form CP 2/3 *[Signature]*