

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-097-20924-00-00  
Spot: N2NENE Sec/Twnshp/Rge: 3-28S-17W  
330 feet from N Section Line, 660 feet from E Section Line  
Lease Name: PYLE Well #: 1-B  
County: KIOWA Total Vertical Depth: 4850 feet

Operator License No.: 5893  
Op Name: PRATT WELL SERVICE, INC.  
Address: PO BOX 847  
PRATT, KS 67124

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		4750		
PROD	4.5	4849	2300	WITH 175 SX CMT
SURF		454		WITH 350 SX CMT

#157<sup>63</sup>

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/20/2005 3:00 PM  
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.  
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 786-2001

Proposed Plugging Method: SAND TO 4665' & 4 SX CMT. PLUG AT 1050' WITH 12 SX GEL & 50 SX CMT. PLUG AT 480' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 10/20/2005 4:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

SANDED BACK TO 4665' & PUT 4 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. SPOT PLUGS THROUGH 4 1/2" CASING. 1ST PLUG AT 1050' WITH 12 SX GEL & 50 SX CMT. 2ND PLUG AT 480' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
4770	4773		
4764	4768		
4715	4724		

INVOICED

DATE 10-31-05  
NOV. 2006 16 06 90

Remarks: USED 60/40 POZMIX 6% GEL BY ACID SERVICE.  
Plugged through: CSG

District: 01



Signed Stephen J. Speck  
(TECHNICIAN)

