

3 022885

To:

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

130 S. Market, Room 2078

Wichita, Kansas 67202

TECHNICIAN'S PLUGGING REPORT

Operator License #

101

Operator: STATE OF KANSAS Fee Fund

Name &

Address

AB oil well ☒ Gas Well ☐ SWD Well/ Input Well ☐

Other well as hereinafter indicated:

Plugging Contractor: KEPLEY WELL SERVICE, LLC

Lic. #

30670

Address: 19245 FORD ROAD, CHANUTE, KANSAS 66720

Company to plug at: Hour: 8:00A.M. Day: 9 Month: 9 2005

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION

Phone:

620-432-2300

Were: THIS WELL CONSISTED O 2 7/8" CASING TO APPROXIMATELY 825' THAT HAD

BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TO

SQUEEZE THE 2 7/8" CASING FULL OF CEMENT FROM SURFACE.

Plugging Proposal Received by:

CLAYTON P. TITEL

Plugging attended by Agent:

All

Part

TECHNICIAN

None

☒

Operations Completed: Hour:

9:00A.M.

Day:

9 Month:

9

2005

Actual Plugging Report:

THE PUMP TRUCK WAS CONNECTED DIRECTLY TO

THE 2 7/8" CASING. CEMENT WAS PUMPED INTO THE 2 7/8" CASING UNTIL THE

WELL WOULD HOLD PRESSURE. THE WELL WAS THEN SHUT IN AT 750PSI.

APPROXIMATELY 35 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

Remarks: (GPS SESSION PT. NO. 30) (WELL NO. 3-API NO. 15-001-24,090)

(If additional description is necessary, use BACK of this form.)

I ☐ DID NOT observe this plugging.

Signed:

Clayton P. Titel
TECHNICIAN

RECEIVED

OCT 11 2005

KCC WICHITA