

3 022892

10-31-05
KCC
Per Footages

15-001-28082-00-00

To:

STATE CORPORATION COMMISSION

API NUMBER
SWSWSE NW
SE, SW, NW 1/4

CONTROL NO. 20050053-033

Sec/Twp/Rge S19-T.26S.-R.18E.

Wichita State Office Bldg. - PLUGGING SECTION

2772 feet from south section line

130 S. Market, Room 2078

3847 feet from east section line

Wichita, Kansas 67202

TECHNICIAN'S PLUGGING REPORT

Lease/Well# KENNITH WOLF NO. 2-32

Operator License # 101

County ALLEN

Operator: STATE OF KANSAS Fee Fund

Well Total Depth 825' feet

Name & _____

Production Pipe: 2 7/8" Size Feet 825'

Address _____

Surface Casing: 6 1/4" Size Feet 20'

AB oil well Gas Well _____ SWD Well/ Input Well _____ D & A _____

Other well as hereinafter indicated: _____

Plugging Contractor: KEPLEY WELL SERVICE, LLC Lic. # 30670

Address: 19245 FORD ROAD, CHANUTE, KANSAS 66720

Company to plug at: Hour: 1:00P.M. Day: _____ 19 Month: 9 2005

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300

Were: THIS WELL CONSISTED OF 2 7/8" CASING TO APPROXIMATELY 825" THAT HAD

BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TO

SQUEEZE THE 2 7/8" CASING FULL OF CEMENT FROM SURFACE.

Plugging Proposal Received by: CLAYTON P. TITEL

Plugging attended by Agent: All _____ Part _____ TECHNICIAN None

Operations Completed: Hour: 2:00P.M. Day: _____ 19 Month: 9 2005

Actual Plugging Report: THE PUMP TRUCK WAS CONNECTED DIRECTLY

TO THE 2 7/8" CASING. CEMENT WAS PUMPED INTO THE 2 7/8" CASING UNTIL

THE WELL WOULD HOLD PRESSURE. THE WELL WAS THEN SHUT IN AT 900PSI.

28 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

Remarks: (GPS SESSION PT. NO.33) (WELL NO. 32-API NO. 15-001-28,082)

(If additional description is necessary, use BACK of this form.)

I DID NOT observe this plugging.

Signed:

Clayton P. Titel
TECHNICIAN

RECEIVED

OCT 11 2005

KCC WICHITA

Bm