

3 022863

KCC  
BEM  
10-31-05  
Per Footages

15-001-27846-00-00

To:

API NUMBER CONTROL NO. 20050053-013

STATE CORPORATION COMMISSION

NE SE, NW, NW 1/4 Sec/Twp/Rge S.19-T.26S.-R.18E.

Wichita State Office Bldg. - PLUGGING SECTION

4417 feet from south section line

130 S. Market, Room 2078

4175 feet from east section line

Wichita, Kansas 67202

TECHNICIAN'S PLUGGING REPORT

Lease/Well# KENNITH WOLF NO.16

Operator License # 101

County ALLEN

Operator: STATE OF KANSAS Fee Fund

Well Total Depth 825' feet

Name & FEE FUND PLUGGING

Production Pipe: 2 7/8" Size Feet 825"

Address \_\_\_\_\_

Surface Casing: 6 1/4" Size Feet 20'

AB oil well  Gas Well \_\_\_\_\_ SWD Well/ Input Well \_\_\_\_\_

D & A \_\_\_\_\_

Other well as hereinafter indicated: \_\_\_\_\_

Plugging Contractor: KEPLEY WELL SERVICE, LLC

Lic. # 30670

Address: 19245 FORD ROAD, CHANUTE, KANSAS 66720

Company to plug at: Hour: 8:00A.M. Day: \_\_\_\_\_ 2 Month: 9 2005

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300

Were: THIS WELL CONSISTED OF 2 7/8" CASING TO APPROXIMATELY 825' THAT

HAD BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS

TO SQUEEZE THE 2 7/8" CASING FULL OF CEMENT FROM SURFACE.

Plugging Proposal Received by: CLAYTON P. TITEL

TECHNICIAN

Plugging attended by Agent: All \_\_\_\_\_ Part \_\_\_\_\_

None

Operations Completed: Hour: 10:00P.M. Day: \_\_\_\_\_ 2 Month: 9 2005

Actual Plugging Report: THE PUMP TRUCK WAS CONNECTED DIRECTLY TO

THE 2 7/8" CASING. COTTON SEED HULLS WERE MIXED WITH THE FIRST OF THE

CEMENT TO BE PUMPED. CEMENT WAS PUMPED INTO THE 2 7/8" CASING UNTIL

THE WELL WOULD HOLD PRESSURE. THE WELL WAS THEN SHUT IN AT 600PSI.

49 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

RECEIVED

KCC WICHITA  
RECEIVED

SEP 19 2005

KCC WICHITA

Remarks: (GPS SESSION PT. NO.13) (API NO.15-001-27864. FOR WELL NO.16)

(If additional description is necessary, use BACK of this form.)

I DID NOT observe this plugging.

Signed:

Clayton P. Titel  
TECHNICIAN

B