

3 022858

15-001-27877-00-00

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER CONTROL NO. 20050053-006
SW,NW,NW 1/4 Sec/Twp/Rge S.19-T.26S.-R.18E.
4392 feet from south section line
4996 feet from east section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 101
Operator: STATE OF KANSAS Fee Fund
Name & FEE FUND PLUGGING
Address _____
AB oil well Gas Well _____ SWD Well/ Input Well _____

Lease/Well# KENNITH WOLF NO.18
County ALLEN
Well Total Depth 825' feet
Production Pipe: 2 7/8" Size Feet 825'
Surface Casing: 6 5/8" Size Feet 20'
D & A _____

Other well as hereinafter indicated: _____
Plugging Contractor: KEPLEY WELL SERVICE,LLC Lic. # 30670

Address: 19245 FORD ROAD, CHANUTE, KANSAS 66720
Company to plug at: Hour: 9:00A.M. Day: _____ 1 Month: 9 2005

Plugging proposal received from: CLAYTON P. TITEL
Company Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300

Were: THIS WELL CONSISTED OF 2 7/8" CASING TO APPROXIMATELY 825' THAT
HAD BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS
TO SQUEEZE THE 2 7/8" CASING FULL OF CEMENT FROM SURFACE.

Plugging Proposal Received by: CLAYTON P. TITEL
TECHNICIAN
Plugging attended by Agent: All Part _____ None _____

Operations Completed: Hour: 11:00A.M. Day: _____ 1 Month: 9 2005

Actual Plugging Report: THE PUMP TRUCK WAS CONNECTED DIRECTLY TO
THE 2 7/8" CASING. COTTON SEED HULLS WERE MIXED WITH THE FIRST OF THE
CEMENT TO BE PUMPED. CEMENT WAS PUMPED INTO THE 2 7/8" CASING UNTIL
THE WELL WOULD HOLD PRESSURE. THE WELL WAS THEN SHUT IN AT 700PSI.
35 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

RECEIVED
SEP 19 2005
KCC WICHITA

Remarks: (GPS SESSION PT. NO.6) (API NO. 15-001-27,877. FOR WELL NO.18)
(If additional description is necessary, use BACK of this form.)

I DID observe this plugging.

Signed: Clayton P. Titel
TECHNICIAN

[Handwritten signature]