

3 022873

KCC
BEM
10-31-05
Per Footages

15-001-27914-00-00

To:

STATE CORPORATION COMMISSION

API NUMBER NW1/4 NE1/4 NE, NE, NW 1/4 CONTROL NO. 20050053-027
Sec/Twp/Rge S.19-T.26S.-R.18E.

Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, Kansas 67202

5096 feet from south section line
3694 feet from east section line

TECHNICIAN'S PLUGGING REPORT

Lease/Well# KENNETH WOLF NO. 21

Operator License # 101

County ALLEN

Operator: STATE OF KANSAS Fee Fund

Well Total Depth 800' feet

Name & FEE FUND PLUGGING

Production Pipe: 2 7/8" Size Feet 800'

Address _____

Surface Casing: 6 1/4" Size Feet 20'

AB oil well Gas Well _____ SWD Well/ Input Well _____ D & A _____

Other well as hereinafter indicated: _____

Plugging Contractor: KEPLEY WELL SERVICE, LLC Lic. # 30670

Address: 19245 FORD ROAD, CHANUTE, KANSAS 66720

Company to plug at: Hour: 10:00AM Day: _____ 8 Month: 9 2005

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300

Were: THIS WELL CONSISTED OF 2 7/8" CASING TO APPROXIMATELY 800'

THAT HAD BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING
PROPOSAL WAS TO SQUEEZE THE 2 7/8" CASING FULL OF CEMENT FROM
SURFACE.

Plugging Proposal Received by: CLAYTON P. TITEL

Plugging attended by Agent: All _____ Part _____
TECHNICIAN
None

Operations Completed: Hour: 12:00P.M. Day: _____ 8 Month: 9 2005

Actual Plugging Report: THE PUMP TRUCK WAS CONNECTED DIRECTLY

TO THE 2 7/8" CASING. COTTON SEED HULLS WERE MIXED WITH THE FIRST OF
THE CEMENT TO BE PUMPED. CEMENT WAS PUMPED INTO THE 2 7/8"
CASING UNTIL THE WELL WOULD HOLD PRESSURE. THE WELL WAS THEN
SHUT IN AT 750PSI. 42 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

Remarks: (GPS SESSION PT. NO.27) (API NO.15-001-27,914. FOR WELL NO.21)
(If additional description is necessary, use BACK of this form.)

I DID NOT observe this plugging.

Signed:

Clayton P. Titel
TECHNICIAN

RECEIVED
SEP 21 2005
KCC WICHITA