

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-175-21612-00-00
Spot: SWNW Sec/Twnshp/Rge: 8-35S-34W
1980 feet from N Section Line, 660 feet from W Section Line
Lease Name: DUNLAP Well #: 2-8
County: SEWARD Total Vertical Depth: 8200 feet

Operator License No.: 5263
Op Name: MIDWESTERN EXPLORATION COMPA
Address: 3500 S BOULEVARD - SUITE 2B
EDMOND, OK 73013

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		6500		
CIBP		6650		
COND	20	70		WITH 7 YDS CMT #266 ⁵⁰
PROD	4.5	6855	1723	WITH 460 SX CMT
SURF	8.625	1620		WITH 521 SX CMT

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 10/06/2005 5:00 PM
Plug Co. License No.: 7407 Plug Co. Name: EAGLE WELL SERVICE
Proposal Rcvd. from: RICKY ESCEBEDO Company: EAGLE WELL SERVICE Phone: (620) 624-1904

Proposed Plugging Method: SPOT 35 SX CMT & HULLS AT 5800'. PLUG AT 1650' WITH 50 SX CMT. PLUG AT 550' WITH 40 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: NONE
Date/Time Plugging Completed: 10/07/2005 7:30 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:

RUN TUBING TO 6050'. CIRCULATE HOLE & PUMP 200# HULLS & 35 SX CMT.
PULL OT OF HOLE WITH TUBING. CUT CASING @ 1723'. 1ST PLUG PULL TO 1650'.
LOAD HOLE & PUMP 50 SX CMT AT 1650'. 2ND PLUG AT 550' WITH 40 SX CMT.
3RD PLUG AT 40' WITH 10 SX CMT.


Perfs:

Top	Bot	Thru	Comments
6676	6682		
6538	6546		
6314	6334	OH	
6290	6296	OH	
6254	6264	OH	
4398	4404		SQ'D W/250 SX
4354	4370		

Remarks: USED COMMON CEMENT BY EAGLE WELL SERVICE.

Plugged through: CSG

District: 01



Signed

Jim Holland (TECHNICIAN) RIRTH

RECEIVED
OCT 27 2005
KCC WICHITA

INVOICED
DATE 10-27-05
INV. NO. 2006060679