

3 022869

KCC  
BEM  
10-31-05  
Per Footages

15-001-28 018-00-00

To:

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

130 S. Market, Room 2078

Wichita, Kansas 67202

API NUMBER  
S2SE NW NW

CONTROL NO. 20050053-014

NE, NW, NW 1/4 Sec/Twp/Rge S.19-T.26S.-R.18E.

4100 feet from south section line

4152 feet from east section line

TECHNICIAN'S PLUGGING REPORT

Lease/Well# KENNITH WOLF NO23

Operator License #

101

County ALLEN

Operator: STATE OF KANSAS Fee Fund

Well Total Depth 800' feet

Name & FEE FUND PLUGGING

Production Pipe: 2 7/8" Size Feet 800'

Address

Surface Casing: 6 1/4 Size Feet 30'

AB oil well X Gas Well SWD Well/ Input Well

D & A

Other well as hereinafter indicated:

Plugging Contractor: KEPLEY WELL SERVICE, LLC

Lic. # 30670

Address: 19245 FORD ROAD, CHANUTE, KANSAS 66720

Company to plug at: Hour: 10:00A.M. Day: 6 Month: 9 2005

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300

Were: THIS WELL CONSISTED OF 2 7/8" CASING TO APPROXIMATELY 800' THAT  
HAD BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS  
TO CIRCULATE THE CASING FULL OF CEMENT.

Plugging Proposal Received by: CLAYTON P. TITEL

TECHNICIAN

None

Plugging attended by Agent: All X Part

Operations Completed: Hour: 12:00P.M. Day: 6 Month: 9 2005

Actual Plugging Report: 1" PIPE WAS RAN INTO THE 2 7/8" PIPE TO 725'.

CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM  
THE 2 7/8" CASING AT SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT  
WAS FILLED FROM SURFACE. 35 SACKS OF CEMENT WERE PUMPED INTO THIS  
WELL.

Remarks: (GPS SESSION PT. NO.14) (API NO.15-001-28,018. FOR WELL NO.23)

(If additional description is necessary, use BACK of this form.)

I DID observe this plugging.

RECEIVED

Signed:

Clayton P. Titel  
TECHNICIAN

SEP 21 2005

KCC WICHITA

Bm