

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-179-21144-00-00
Spot: E2NWSW Sec/Twnshp/Rge: 2-10S-29W
2040 feet from S Section Line, 930 feet from W Section Line
Lease Name: BIXENMAN BROTHERS Well #: 1
County: SHERIDAN Total Vertical Depth: 4230 feet

Operator License No.: 31900
Op Name: NOR-WEST KANSAS OIL, L.L.C.
Address: RR 2, BOX 14
WAKEENEY, KS 67672

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	265		

137⁴⁸

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 10/25/2005 12:00 PM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: GREG Company: NOR-WEST KANSAS OIL, LLC Phone: (785) 743-2769

Proposed Plugging Method: Ordered out 200 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: BRUCE BASYE WitnessType: NONE
Date/Time Plugging Completed: 10/25/2005 1:15 PM KCC Agent: BRUCE BASYE

Actual Plugging Report:

1st. Plug at 2420' w/25 sxs.
2nd. Plug at 1530' w/100 sxs.
3rd. Plug at 315' w/40 sxs.
4th. Plug at 40' w/10 sxs.
Rathole with 15 sxs.
Mousehole with 10 sxs.

Perfs:

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed

Bruce D. Basye
(TECHNICIAN)

INVOICED

DATE 10-27-05
INVOICE NO. 2006060680

RECEIVED

OCT 27 2005

KCC WICHITA

Form CP-2/3

OCT 26 2005