

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-145-00168-00-01
Spot: NENESW Sec/Twnshp/Rge: 2-23S-16W
2310 feet from S Section Line, 2970 feet from E Section Line
Lease Name: ZOOK OWWO Well #: 1
County: PAWNEE Total Vertical Depth: 4139 feet

Operator License No.: 8061
Op Name: OIL PRODUCERS INC. OF KANSAS
Address: 1710 WATERFRONT PARKWAY
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	4138	0	WITH 275 SX CMT
SURF	8.625	200		WITH 160 SX CMT

#134 52

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/17/2005 1:30 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: JOE MAES Company: QUALITY WELL SERVICE, INC. Phone: (620) 786-2001

Proposed Plugging Method: PLUG AT 2970' WITH 20 SX GEL & 25 SX CMT. PLUG AT 1000' WITH 25 SX CMT. PLUG AT 240-0' WITH 25 SX CMT. TOP OFF WITH 5 SX CMT. CHECK BACKSIDE.

Plugging Proposal Received By: RICHARD LACEY WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/17/2005 4:45 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

SQUEEZED @ 2602-2633' WITH 50 SX CMT. SQUEEZED @ 824-885' & 1111-1141' WITH 400 SX CMT. 1ST PLUG AT 3970' WITH 20 SX GEL - 25 SX CMT. 2ND PLUG AT 1000' WITH 25 SX CMT THROUGH TUBING. 3RD PLUG AT 240-0' WITH 25 SX CMT THROUGH TUBING. 4TH PLUG PULLED TUBING & TOPPED OFF WITH 5 SX CMT. PUMPED DOWN 8 5/8" X 4 1/2" CASING WITH 25 SX CMT. BLEW HOLE IN SURFACE PIPE.

Perfs:


Top	Bot	Thru	Comments
3988	3993		
3976	3978		
3967	3968		

Remarks: USED 60/40 POZMIX 6% GEL BY ACID SERVICE.

Plugged through: TBG

INVOICE
DATE 10-27-05
WEL. NO. 2006060681

District: 01



Signed

Richard W. Lacey
(TECHNICIAN)

RECEIVED
OCT 27 2005
KCC WICHITA