

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-145-21128-00-01
Spot: NENENW Sec/Twnshp/Rge: 2-20S-16W
4950 feet from S Section Line, 2970 feet from E Section Line
Lease Name: RYAN SWD Well #: 1
County: PAWNEE Total Vertical Depth: 4340 feet

Operator License No.: 30337
Op Name: SPECIAL ENERGY CORP.
Address: PO BOX 369
STILLWATER, OK 74076

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		3800		WITH 7 SX CMT
PKR		3850		
PROD	7.625	3894	1600	WITH 200 SX CMT
SURF	10.75	1018		

\$141⁰⁵

Well Type: SWD UIC Docket No: D27910.0 Date/Time to Plug: 10/14/2005 12:00 PM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: JOE MAES Company: QUALITY WELL SERVICE, INC. Phone: (620) 786-2001

Proposed Plugging Method: CIBP @ 3800' WITH 7 SX CMT. PLUG AT 1050' WITH 38 SX GEL - 60 SX CMT. PLUG AT 660' WITH 50 SX CMT. PLUG AT 60' WITH 20 SX CMT.

Plugging Proposal Received By: STEVE DURRANT WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 10/14/2005 1:15 PM KCC Agent: RICHARD LACEY

Actual Plugging Report:

LEFT MOST OF PACKER IN HOLE @ 3850'. 1ST PLUG SET CIBP @ 3800' WITH 7 SX CMT. SET PLUGS THROUGH TUBING. 2ND PLUG AT 1050' WITH 38 SX GEL - 60 SX CMT. 3RD PLUG AT 660' WITH 50 SX CMT. 4TH PLUG AT 60' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3894	4340	OH	

INVOICED
DATE 10-27-05
INV. NO. 2006060683

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED.
Plugged through: TBG

District: 01
RECEIVED
OCT 20 2005
KCC Dodge City

Signed Richard W. Lacey
(TECHNICIAN)

RECEIVED
OCT 27 2005
KCC WICHITA

Form CP-272