

3 022870

KCC
10-31-05
BEM
Perforations

15-001-27988-00-00
CONTROL NO. 20050053-023

To:

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

130 S. Market, Room 2078

Wichita, Kansas 67202

API NUMBER
NW, NE, SW, NW
NW, SW, NW 1/4

Sec/Twp/Rge S.19-T.26S.-R.18E.

3749 feet from south section line

4529 feet from east section line

TECHNICIAN'S PLUGGING REPORT

Lease/Well# KENNITH WOLF NO. 25

Operator License # 101

County ALLEN

Operator: STATE OF KANSAS Fee Fund

Well Total Depth 810' feet

Name & FEE FUND PLUGGING

Production Pipe: 2 7/8" Size Feet 810'

Address

Surface Casing: 6 1/4 Size Feet 30'

AB oil well X Gas Well SWD Well/ Input Well

D & A

Other well as hereinafter indicated:

Plugging Contractor: KEPLEY WELL SERVICE, LLC

Lic. # 30670

Address: 19245 FORD ROAD, CHANUTE, KANSAS 66720

Company to plug at: Hour: 2:00P.M. Day: 6 Month: 9 2005

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300

Were: THIS WELL CONSISTED OF 2 7/8" CASING TO APPROXIMATELY 800' THAT

HAD BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS

TO CIRCULATE THE CASING FULL OF CEMENT.

Plugging Proposal Received by: CLAYTON P. TITEL

TECHNICIAN

Plugging attended by Agent: All Part None X

Operations Completed: Hour: 3:00P.M. Day: 6 Month: 9 2005

Actual Plugging Report: 1" PIPE WAS RAN INTO THE 2 7/8" PIPE TO 810'.

CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM

THE 2 7/8" CASING AT SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT

WAS FILLED FROM SURFACE. 36 SACKS OF CEMENT WERE PUMPED INTO THIS

WELL.

Remarks: (GPS SESSION PT. NO.23) (API NO.15-001-27,988. FOR WELL NO.25)

(If additional description is necessary, use BACK of this form.)

I DID NOT observe this plugging.

Signed:

Clayton P. Titel
TECHNICIAN

RECEIVED

SEP 21 2005

KCC WICHITA