

3 022880

15-207-19617-000

To:

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

130 S. Market, Room 2078

Wichita, Kansas 67202

API NUMBER CONTROL NO. 20050019-054

SW,SE,NE 1/4 Sec/Twp/Rge S28-T.25S.-R.17E.

2767 feet from south section line

1186 feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License #

101

Lease/Well# WILLIAMS NO.33

County WOODSON

Operator: STATE OF KANSAS Fee Fund

Well Total Depth 750' feet

Name &amp; FEE FUND PLUGGING

Production Pipe: Size Feet

Address

Surface Casing: 12" Size Feet 20'

AB oil well X Gas Well SWD Well/ Input Well

D &amp; A

Other well as hereinafter indicated:

Plugging Contractor: K-W WELL SERVICE, INC.

Lic. #

3097

Address: 19450 FORD ROAD, CHANUTE, KANSAS 66720

Company to plug at: Hour: 8:00A.M. Day: 22 Month: 9 2005

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION

Phone:

620-432-2300

Were: THIS WELL CONTAINED NO EVIDENT CASINGS. THE PLUGGING PROPOSAL

WAS TO INSTALL SURFACE CASING, DRILL OUT THE WELL, AND TO CIRCULATE AS MUCH OF  
THE WELL AS POSSIBLE FULL OF CEMENT.

Plugging Proposal Received by:

CLAYTON P. TITEL

TECHNICIAN

Plugging attended by Agent: All Part

None X

Operations Completed: Hour: 11:00P.M. Day: 22 Month: 9 2005

Actual Plugging Report: 20' OF 12" SURFACE CASING WAS INSTALLED IN THE WELL.

THE WELL WAS DRILLED OUT TO 380'. AT THAT DEPTH IRON WAS ENCOUNTERED AND

PROGRESS WAS HALTED. 1" PIPE WAS WASHED INTO THE WELL TO 650'. CEMENT WAS

PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE SURFACE CASING AT

SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE.

260 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

Remarks: (GPS SESSION PT. NO.33) (THIS WELL WAS NOT ILLUSTRATED ON THE LEASE MAP.)

(If additional description is necessary, use BACK of this form.)

I DID NOT observe this plugging.

RECEIVED

Signed:

OCT 11 2005

KCC WICHITA

*Clayton P. Titel*  
TECHNICIAN

*B*