

3 022866

10-31-05  
Kee  
Benn  
Per Footages

15-001-28025-00-00  
CONTROL NO. 20050053-016

To:

API NUMBER

STATE CORPORATION COMMISSION

SE, NE, SW, NW 1/4

Sec/Twp/Rge

S.19-T.26S.-R.18E.

Wichita State Office Bldg. - PLUGGING SECTION

3430 feet from south section line

130 S. Market, Room 2078

4152 feet from east section line

Wichita, Kansas 67202

TECHNICIAN'S PLUGGING REPORT

Lease/Well#

KENNITH WOLF NO. 28

Operator License #

101

County

ALLEN

Operator: STATE OF KANSAS Fee Fund

Well Total Depth

800' feet

Name & FEE FUND PLUGGING

Production Pipe:

2 7/8" Size Feet 800'

Address

Surface Casing:

6 1/4 Size Feet 30'

AB oil well

Gas Well

SWD Well/ Input Well

D & A

Other well as hereinafter indicated:

Plugging Contractor: KEPLEY WELL SERVICE, LLC

Lic. #

30670

Address: 19245 FORD ROAD, CHANUTE, KANSAS 66720

Company to plug at:

Hour: 8:00A.M. Day:

6 Month:

9

2005

Plugging proposal received from: CLAYTON P. TITEL

Company Name:

KANSAS CORPORATION COMMISSION

Phone:

620-432-2300

Were:

THIS WELL CONSISTED OF 2 7/8" CASING TO APPROXIMATELY 800' THAT

HAD BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS

TO CIRCULATE THE CASING FULL OF CEMENT.

Plugging Proposal Received by:

CLAYTON P. TITEL

Plugging attended by Agent:

All

Part

TECHNICIAN

None

Operations Completed: Hour:

10:00A.M. Day:

6 Month:

9

2005

Actual Plugging Report:

1" PIPE WAS RAN INTO THE 2 7/8" PIPE TO 775'.

CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM

THE 2 7/8" CASING AT SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT

WAS FILLED FROM SURFACE. 28 SACKS OF CEMENT WERE PUMPED INTO THIS

WELL.

Remarks: (GPS SESSION PT. NO.16) (API NO.15-001-28,205 FOR WELL NO.28)

(If additional description is necessary, use BACK of this form.)

I

DID

observe this plugging.

Signed:

Clayton P. Titel  
TECHNICIAN

RECEIVED

SEP 21 2005

KCC WICHITA

Bm