

3 022889

10-31-05  
KCC  
BEM  
Per Footages  
SW

15-001-28081-00-00

To:

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

130 S. Market, Room 2078  
Wichita, Kansas 67202

API NUMBER  
NE,NW,NW 1/4

CONTROL NO. 20050053-017

Sec/Twp/Rge S19-T.26S.-R.18E.

3470 feet from south section line

3829 feet from east section line

TECHNICIAN'S PLUGGING REPORT

Lease/Well# KENNITH WOLF NO.31

Operator License #

101

County ALLEN

Operator: STATE OF KANSAS Fee Fund

Well Total Depth 825' feet

Name &

Production Pipe: 2 7/8" Size Feet 825'

Address

Surface Casing: 6 1/4" Size Feet 20

AB oil well X Gas Well SWD Well/ Input Well D & A

Other well as hereinafter indicated:

Plugging Contractor: KEPLEY WELL SERVICE, LLC

Lic. # 30670

Address: 19245 FORD ROAD, CHANUTE, KANSAS 66720

Company to plug at: Hour: 11:00A.M. Day: 19 Month: 9 2005

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300

Were: THIS WELL CONSISTED OF 2 7/8" CASING TO APPROXIMATELY 825" THAT HAD BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TO CIRCULATE THE 2 7/8" CASING FULL OF CEMENT.

Plugging Proposal Received by: CLAYTON P. TITEL

Plugging attended by Agent: All Part None X

TECHNICIAN

Operations Completed: Hour: 2:00A.M. Day: 19 Month: 9 2005

Actual Plugging Report: 1" PIPE WAS RAN INTO THE 2 7/8" CASING TO 775'.

CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 2 7/8" CASING AT SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE. 49 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

Remarks: ( GPS SESSION PT. NO.17 ) ( WELL NO. 31-API NO. 15-001-28.081 )

(If additional description is necessary, use BACK of this form.)

I DID NOT observe this plugging.

Signed:

Clayton P. Titel  
TECHNICIAN

RECEIVED  
OCT 11 2005  
KCC WICHITA