

3 022882

10:31-05
KCC
BEM
Per Footages
NW SE

15-001-28047-00-00

To:

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

130 S. Market, Room 2078

Wichita, Kansas 67202

API NUMBER

CONTROL NO. 20050053-018

NE,SW,NW 1/4

Sec/Twp/Rge S19-T.26S.-R.18E.

3810 feet from south section line

3813 feet from east section line

TECHNICIAN'S PLUGGING REPORT

Lease/Well#

KENNITH WOLF NO.30

Operator License #

101

County

ALLEN

Operator: STATE OF KANSAS Fee Fund

Well Total Depth

825' feet

Name &

Production Pipe: 2 7/8"

Size Feet 825'

Address

Surface Casing: 6 1/4"

Size Feet 20'

AB oil well

Gas Well

SWD Well/ Input Well

D & A

Other well as hereinafter indicated:

Plugging Contractor: KEPLEY WELL SERVICE, LLC

Lic. #

30670

Address: 19245 FORD ROAD, CHANUTE, KANSAS 66720

Company to plug at:

Hour: 8:00A.M. Day:

15 Month:

9

2005

Plugging proposal received from: CLAYTON P. TITEL

Company Name:

KANSAS CORPORATION COMMISSION

Phone:

620-432-2300

Were:

THIS WELL CONSISTED O 2 7/8" CASING TO APPROXIMATELY 825' THAT HAD

BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TO

CIRCULATE THE 2 7/8" CASING FULL OF CEMENT.

Plugging Proposal Received by:

CLAYTON P. TITEL

Plugging attended by Agent:

All

Part

TECHNICIAN

None

Operations Completed: Hour:

11:00A.M. Day:

15 Month:

9

2005

Actual Plugging Report:

1" PIPE WAS RAN INTO THE 2 7/8" CASING TO 800'.

CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE

2 7/8" CASING AT SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT WAS

FILLED FROM SURFACE. APPROXIMATELY 30 SACKS OF CEMENT WERE PUMPED

INTO THIS WELL.

Remarks: (GPS SESSION PT. NO.18) (WELL NO. 30-API NO. 15-001-28047)

(If additional description is necessary, use BACK of this form.)

I

DID

observe this plugging.

Signed:

Clayton P. Titel

TECHNICIAN

RECEIVED

OCT 11 2005

KCC WICHITA