

3 022886

10-31-05
KCC
BEING
Perforated

15-001-27847-00-00

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER CONTROL NO. 20050053-031
NW,NE,NW 1/4 Sec/Twp/Rge S19-T.26S.-R.18E.
4804 feet from south section line
3480 feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 101
Operator: STATE OF KANSAS Fee Fund

Lease/Well# KENNITH WOLF NO.17
County ALLEN
Well Total Depth 825' feet
Production Pipe: 2 7/8" Size Feet 825'
Surface Casing: 6 1/4" Size Feet 20

Name & _____
Address _____

AB oil well Gas Well _____ SWD Well/ Input Well _____ D & A _____

Other well as hereinafter indicated: _____

Plugging Contractor: KEPLEY WELL SERVICE, LLC Lic. # 30670

Address: 19245 FORD ROAD, CHANUTE, KANSAS 66720

Company to plug at: Hour: 8:00A.M. Day: _____ 8 Month: 9 2005

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300

Were: THIS WELL CONSISTED O 2 7/8" CASING TO APPROXIMATELY 825' THAT HAD BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TO SQUEEZE THE 2 7/8" CASING FULL OF CEMENT FROM SURFACE.

Plugging Proposal Received by: CLAYTON P. TITEL

Plugging attended by Agent: All _____ Part _____ Technician X

Operations Completed: Hour: 11:00A.M. Day: _____ 8 Month: 9 2005

Actual Plugging Report: THE PUMP TRUCK WAS CONNECTED DIRECTLY TO THE 2 7/8" CASING. CEMENT WAS PUMPED INTO THE 2 7/8" CASING UNTIL THE WELL WOULD HOLD PRESSURE. THE WELL WAS THEN SHUT IN AT 700PSI. APPROXIMATELY 35 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

Remarks: (GPS SESSION PT. NO.31) (WELL NO. 17-API NO. 15-001-27,847)
(If additional description is necessary, use BACK of this form.)

I DID NOT observe this plugging.

Signed: Clayton P. Titel
TECHNICIAN

RECEIVED
OCT 11 2005
KCC WICHITA