

3 022881

15-001-28198-00.00

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, Kansas 67202

API NUMBER CONTROL NO. 20050053-019
NW,SE,NW 1/4 Sec/Twp/Rge S19-T.26S.-R.18E.
3819 feet from south section line
3489 feet from east section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 101
Operator: STATE OF KANSAS Fee Fund

Lease/Well# KENNITH WOLF NO.33
County ALLEN
Well Total Depth 825' feet
Production Pipe: 2 7/8" Size Feet 825'
Surface Casing: 6 1/4" Size Feet 20'

Name & _____
Address _____
AB oil well X Gas Well _____ SWD Well/ Input Well _____

D & A _____

Other well as hereinafter indicated: _____

Plugging Contractor: KEPLEY WELL SERVICE, LLC Lic. # 30670

Address: 19245 FORD ROAD, CHANUTE, KANSAS 66720

Company to plug at: Hour: 8:00A.M. Day: _____ 14 Month: 9 2005

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300

Were: THIS WELL CONSISTED O 2 7/8" CASING TO APPROXIMATELY 825' THAT HAD BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TO CIRCULATE THE 2 7/8" CASING FULL OF CEMENT.

Plugging Proposal Received by: CLAYTON P. TITEL

Plugging attended by Agent: All _____ Part _____ TECHNICIAN None X

Operations Completed: Hour: 10:00A.M. Day: _____ 14 Month: 9 2005

Actual Plugging Report: 1" PIPE WAS RAN INTO THE 2 7/8" CASING TO 800'.

CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE 2 7/8" CASING AT SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE. APPROXIMATELY 30 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

Remarks: (GPS SESSION PT. NO.19) (WELL NO. 33-API NO. 15-001-28198)

(If additional description is necessary, use BACK of this form.)

I DID NOT observe this plugging.

Signed:

Clayton P. Titel
TECHNICIAN

RECEIVED
OCT 11 2005
KCC WICHITA

Bur