

KANSAS CORPORATION COMMISSION  
OIL & GAS CONSERVATION DIVISION  
**WELL PLUGGING APPLICATION**  
Please TYPE Form and File ONE Copy

Form CP-1  
September 2003  
This Form must be Typed  
Form must be Signed  
All blanks must be Filled

API # 15 - 007-22,309-00-00 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued, indicate original spud or completion date 04/1990.

Well Operator: F.G. Holl Company, L.L.C. KCC License #: 5056  
(Owner / Company Name) (Operator's)

Address: 9431 E. Central, St. 100 City: Wichita

State: Kansas Zip Code: 67206 Contact Phone: (316) 684-8481

Lease: LAMBERT D2 Well #: 1-4 Sec. 4 Twp. 30 S. R. 13  East  West

14'S & 14'E N/2 - SW - SW Spot Location / QQQQ County: Barber

976 Feet (in exact footage) From  North /  South (from nearest outside section corner) Line of Section (Not Lease Line)

646 Feet (in exact footage) From  East /  West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One:  Oil Well  Gas Well  D&A  Cathodic  Water Supply Well  
 SWD Docket # \_\_\_\_\_  ENHR Docket # \_\_\_\_\_  Other: \_\_\_\_\_

Conductor Casing Size: 13-3/8" Set at: 150' Cemented with: 140 Sacks

Surface Casing Size: 8-5/8" Set at: 1144' Cemented with: 425 Sacks

Production Casing Size: 4-1/2" Set at: 4747' Cemented with: 275 Sacks

List (ALL) Perforations and Bridgeplug Sets: 4449'-4468', 4534'-4536', 4538'-4540', 4543'-4545', 4549'-4555'.

Elevation: 1896 ( G.L. /  K.B.) T.D.: 4764' PBDT: 4717' Anhydrite Depth: 17835' Est.  
(Stone Corral Formation)

Condition of Well:  Good  Poor  Casing Leak  Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed):

Heavy Mud, hulls, cement and plug according to KCC regulations.

Is Well Log attached to this application as required?  Yes  No Is ACO-1 filed?  Yes  No

If not explain why? \_\_\_\_\_

RECEIVED  
NOV 07 2005  
KCC WICHITA

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Rob Long

Phone: (620) 793-0915/786-5783

Address: P.O. Box 158 City / State: Belpre, KS. 67519

Plugging Contractor: Quality Well Service KCC License #: 31925  
(Company Name) (Contractor's)

Address: 401 West Main, Lyson, KS. 67554 Phone: (620) 727-3410

Proposed Date and Hour of Plugging (if known?): Not known

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent  
Date: 11/03/2005 Authorized Operator / Agent: Loveness Manje  
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

6/06

8/06

DRILLERS WELL LOG

F.G. HOLL COMPANY

LAMBERT D-2 #1-4  
Pratt County, Kansas

COMMENCED: April 13, 1990  
COMPLETED: April 24, 1990

0' - 1150' Surface  
1150' - 2125' Shale  
2125' - 3260' Shale & Lime  
3260' - 4155' Shale  
4155' - 4630' Lime & Shale  
4630' - 4765' Shale & Lime  
4765' RTD

Conductor Casing: Set 3 jts. 13-3/8 inch at 150 feet w/140 sacks 60/40 Pozmix, 3% cc.

Surface Casing: Set 26 jts. 8-5/8 inch at 1144 feet 2/425 sacks Halliburton Lite, 3% cc., and 150 sacks 60/40 Pozmix 2% gel, 3% cc.


Production casing: Set 113 jts. 4 1/2 inch 10/5# at 4747' w/115 sacks Lite and 150 sacks 50/50 Pozmix, 18% salt, .75% CFT-3, 5# gilsonite per sack, 1/8# Flocele, 1/8# Tuf Fiber.

RECEIVED  
NOV 07 2005  
KCC WICHITA

AFFIDAVIT

STATE OF KANSAS ]  
] SS:  
COUNTY OF SEDGWICK ]

Alan D. Banta, of lawful age, does swear and state that the facts and statements herein are true and correct to the best of his knowledge.



*Alan D. Banta*  
\_\_\_\_\_  
Alan D. Banta

Subscribed and sworn to me this 30<sup>th</sup> day of April, 1990.

My Commission Expires: May 13, 1991

*Sondra J. Follis*  
\_\_\_\_\_  
NOTARY PUBLIC

KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor

Brian J. Moline, Chair

Robert E. Krehbiel, Commissioner

Michael C. Moffet, Commissioner

**NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)**

November 08, 2005

Holl, F.G., Company L.L.C.  
9431 E Central, Suite 100  
Wichita, KS 67206

Re: LAMBERT D-2 #1-4  
API 15-007-22309-00-00  
N2SWSW 4-30S-13W, 976 FSL 4634 FEL  
BARBER COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.


Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

**Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.**

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

**This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.**

Sincerely

  
David P. Williams  
Production Supervisor

District: #1  
210 E Frontview, Suite A  
Dodge City, KS 67801  
(620) 225-8888