

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING APPLICATION
Please TYPE Form and File ONE Copy

Form CP-1
September 2003
This Form must be Typed
Form must be Signed
All blanks must be Filled

API # 15 - 151-22, 035-0001 (Identifier Number of this well). This must be listed for wells drilled since 1967; if no API # was issued, indicate original spud or completion date 3/29/1991.

Well Operator: F.G. Holl Company, L.L.C. KCC License #: 5056 le/04

Address: 9431 E. Central, St. 100 City: Wichita (Operator's)

State: Kansas Zip Code: 67206 Contact Phone: (316) 684 - 8481

Lease: DORIS LAMBERT "A" Well #: 1-31 Sec. 31 Twp. 29 S. R. 13 East West

156'S & 106'E of C. NW - NE Spot Location / QQQQ County: Pratt

816 Feet (in exact footage) From North / South (from nearest outside section corner) Line of Section (Not Lease Line)

1874 Feet (in exact footage) From East / West (from nearest outside section corner) Line of Section (Not Lease Line)

Check One: Oil Well Gas Well D&A Cathodic Water Supply Well
 SWD Docket # _____ ENHR Docket # _____ Other: _____

Conductor Casing Size: _____ Set at: _____ Cemented with: _____ Sacks

Surface Casing Size: 13-3/8" Set at: 280' Cemented with: 275 Sacks

Production Casing Size: 4-1/2" Set at: 4789' Cemented with: 225 Sacks

List (ALL) Perforations and Bridgeplug Sets: 4013'-4015', 4311'-4318', CIBP @ 4300' & 4540'.

Elevation: 1924 (G.L. / K.B.) T.D.: 4800' PBDT: 4300' Anhydrite Depth: 755'
(Stone Corral Formation)

Condition of Well: Good Poor Casing Leak Junk in Hole

Proposed Method of Plugging (attach a separate page if additional space is needed): _____

Heavy Mud, hulls, cement and plug according to KCC regulations.

Is Well Log attached to this application as required? Yes No Is ACO-1 filed? Yes No

If not explain why? _____

Plugging of this Well will be done in accordance with K.S.A. 55-101 et. seq. and the Rules and Regulations of the State Corporation Commission.

List Name of Company Representative authorized to be in charge of plugging operations: Rob Long

Phone: (620) 793 - 0915/786-5783

Address: P.O. Box 158 City / State: Belpre, KS. 67519

Plugging Contractor: Quality Well Service KCC License #: 31925 8/04

Address: 401 West Main, Lyson, KS. 67554 Phone: (620) 727 - 3410 (Contractor's)

Proposed Date and Hour of Plugging (if known?): Not known

Payment of the Plugging Fee (K.A.R. 82-3-118) will be guaranteed by Operator or Agent

Date: 11/03/2005 Authorized Operator / Agent: Lorenas Mpanje
(Signature)

Mail to: KCC - Conservation Division, 130 S. Market - Room 2078, Wichita, Kansas 67202

STERLING DRILLING COMPANY

BOX 129

STERLING, KANSAS 67579

WELL LOG - - - - - DORIS LAMBERT "A" 1-31

Located: 150' SE of NW NE, section 31-29S-13W, Pratt County, Kansas

OWNER: F. G. Holl Company

DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: February 15, 1991

COMPLETED: February 26, 1991

TOTAL DEPTH: 4800'

LOG

0 - 180 Surface Soil and Sand
180 - 285 Red Bed
285 - 630 Shale, Red Beds
630 - 1295 Shale
1295 - 4800 Lime and Shale

CASING RECORD

Ran 6 joints new 13 3/8", 48# casing.
268.38' pipe set at 280' K.B.
Cemented with 275 sacks 60/40 Pozmix,
2% gel and 3% cc. Plug down at
4:00 PM, 2-15-91, by Howco.

Ran 108 joints 4 1/2", 10.5# new and
used casing. (634.70' used) 4789.19'
pipe set at 4789' K.B. Cemented with
100 sacks Lite followed with 125 sacks
F. G. Holl Mix, with 20 bbl. salt
flush and 500 gal. super flush ahead
of cement. Plug down at 2:45 AM,
2-26-91, by Howco.

RECEIVED
NOV 07 2003
KCC WICHITA

Deviation Survey: 1/2° at 4046'

KANSAS

CORPORATION COMMISSION

Kathleen Sebelius, Governor Brian J. Moline, Chair Robert E. Krehbiel, Commissioner Michael C. Moffet, Commissioner

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

Holl, F.G., Company L.L.C.
9431 E Central, Suite 100
Wichita, KS 67206

November 08, 2005

Re: DORIS LAMBERT A #1-31
API 15-151-22035-00-01
NWNE 31-29S-13W, 4464 FSL 1874 FEL
PRATT COUNTY, KANSAS

Dear Operator:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely



David P. Williams
Production Supervisor

District: #1
210 E Frontview, Suite A
Dodge City, KS 67801
(620) 225-8888