

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-20324-00-00
Spot: SESWNE Sec/Twnshp/Rge: 12-10S-24W
2970 feet from S Section Line, 1650 feet from E Section Line
Lease Name: SE GANO UNIT Well #: 4-2
County: GRAHAM Total Vertical Depth: 4070 feet

Operator License No.: 30606
Op Name: MURFIN DRILLING CO., INC.
Address: 250 N. WATER, STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	4069	0	200 SX CEMENT
SURF	8.625	217	0	150 SX CEMENT

\$132²⁸

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/28/2005 8:00 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: JOHN GERSTNER Company: MURFIN DRILLING CO., INC. Phone: (785) 421-2103

Proposed Plugging Method: Ordered 300 sxs cement and 600# hulls.
Perforated 4 1/2" casing at 1275' and 2140'.

Plugging Proposal Received By: ROGER MOSES Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/28/2005 11:30 AM KCC Agent: ROGER MOSES

Actual Plugging Report:

Ran tubing to 3100' - spotted 75 sxs cement with 300# hulls.
Pulled tubing to 1560' - circulated with 125 sxs cement with 200# hulls.
Pulled all tubing and squeezed 4 1/2" casing with 50 sxs cement.
Max. P.S.I. 500#. S.I.P. 400#.
Tied to 8 5/8" x 4 1/2" annulus - squeezed 50 sxs cement with 100# hulls.
Max. P.S.I. 200#. S.I.P. 100#.
Total of 300 sxs 60/40 pozmix - 10% gel and 600# hulls.

Perfs:

Top	Bot	Thru	Comments
4002	4006		
3978	3983		
3959	3963		
3939	3943		
3898	3904		
3888	3892		
3848	3850		
3840	3844		
3810	3814		

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed Roger Moses
(TECHNICIAN)

INVOICED
DATE 11-4-05
QU. NO. 2006060708

RECEIVED
NOV 04 2005
KCC WICHITA

Form CP-2/3

NOV 03 2005

DON E. PRATT
HAYS, KANSAS

#2 A. E. GANO

12-10-24W
SE SW NE

CONTR L. J. DREILING & SONS

CTY GRAHAM

GEOL

FIELD GANO SE

E 2467 KB CM 5/2/70 CARD ISSUED 6/4/70 IP P 99 BOPD, N/W
LKC 3978-83

API 15-065-20,324

LOG	TOPS	DEPTH	DATUM
TOP		3552	-1085
HEEB		3762	-1295
TOR		3788	-1321
LKC		3809	-1342
LTD		4070	-1603
RTD		4070	-1603

8 5/8" 217/150SX; 4 1/2" 4069/200SX
DST(1) 3799-3846/1', 15' M(VSSO) FBHP
711#, FFP 48#
DST(2) 3844-71/1', 25' OIL SP M W/OIL SC,
BHP 129-96#/30" FP 32-32#
DST(3) 3868-3925/90", 300' M W/SO, BHP
922-873#/30", FP 64-20#
DST(4) 3917-90/90", 70' M W/VSSO, BHP
654-241#/30", FP 80-97#
MICT CO 4042, PF 20/3978-83(LKC) A300
SWB DWN & SWB 9.36BOPH OB + LD(SHORT
18BL) A1700CRA SD/12HRS FU 800' FIH, SWB
5HRS 36 BOPH/1ST HR DECL TO 12 1/2 BOPH,
N/W, POP

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS