

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-065-20264-00-00  
Spot: NWNWSW Sec/Twnshp/Rge: 12-10S-24W  
2310 feet from S Section Line, 4950 feet from E Section Line  
Lease Name: SE GANO UNIT Well #: 2-6  
County: GRAHAM Total Vertical Depth: 4090 feet

Operator License No.: 30606  
Op Name: MURFIN DRILLING CO., INC.  
Address: 250 N. WATER, STE 300  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	4075	0	225 SX CEMENT
SURF	8.625	203	0	150 SX CEMENT

*\$132<sup>93</sup>*

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/27/2005 8:30 AM  
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.  
Proposal Rcvd. from: JOHN GERSTNER Company: MURFIN DRILLING CO., INC. Phone: (785) 421-2103

Proposed Plugging Method: Ordered 300 sxs cement and 600# hulls.  
Perforated at 1275'.

Plugging Proposal Received By: HERB DEINES WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 10/27/2005 12:00 PM KCC Agent: ROGER MOSES

**Actual Plugging Report:**

Squeezed at 1965' w/300 sxs cement.  
Ran tubing to 3101' - spotted 75 sxs cement with 300# hulls.  
Pulled tubing to 1560' - circulated with 75 sxs cement with 200# hulls.  
Pulled all tubing - squeezed 4 1/2" casing with 20 sxs cement.  
Max. P.S.I. 600#. S.I.P. 300#.  
Tied to annulus - squeezed 50 sxs cement with 100# hulls.  
Max. P.S.I. 100#. S.I.P. 100#.  
Total of 220 sxs 60/40 pozmix - 10% gel and 600# hulls.

**Perfs:**

Top	Bot	Thru	Comments
4024	4030		
3984	3990		
3962	3970		
3909	3915		
3898	3902		
3871	3877		
3828	3832		
3813	3817		

Remarks: LEASE ALSO KNOWN AS BEESLEY #6. ALLIED CEMENTING COMPANY.

Plugged through: TBG

District: 04

Signed Roger L. Moses  
(TECHNICIAN)


OCT 31 2005

INVOICED  
DATE 11-4-05  
NOV 04 2005  
2006060708

RECEIVED  
NOV 04 2005  
KCC WICHITA

# INDEXED

DON E. PRATT #6 BEESLEY 12-10-24W  
 HAYS, KS. NW NW SW  
 Contr. GARVEY DRILG. COMPANY Cty. GRAHAM  
 Geol. J.R. GREEN Pool GANO SE  
 E. 2497 KB Cm. 10/16/69 Cp. 12/18/69 IP PMP 180 BOPD  
 API 15-065-20,264 N/W LANS 3871-77  
 GR 41



LOG Tops	Depth	Datum
ANH	2109	+ 388
B ANH	2144	+ 353
TOP	3568	-1071
HEEB	3784	-1287
TOR	3809	-1312
LANS	3822	-1325
BKC	4051	-1554
RID	4090	-1593

Csg. 8-5/8" 203/150 SX  
 4 1/2" 4075/225 SX  
 DST 3815-90/60", GTS/25",  
 3180' SMC&GCO, BHP 1187-  
 1187#/30", FP 515-1147#  
 MICT, CO & PF 24/3871-77, FU  
 3200' OIL/12 HRS, SWB 36 BOPH  
 NAT N/W, N/T, A 500; NO TST,  
 POP  
 NO CORES

INDEPENDENT OIL & GAS SERVICE  
 WICHITA, KANSAS