

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-02801-00-00
Spot: S2SESW Sec/Twnshp/Rge: 4-9S-23W
330 feet from S Section Line, 3300 feet from E Section Line
Lease Name: BUSH CREEK UNIT Well #: 105
County: GRAHAM Total Vertical Depth: 3838 feet

Operator License No.: 5088
Op Name: DARRAH, JOHN JAY, JR.
Address: 225 NORTH MARKET, STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3838	0	UNKNOWN
SURF	8.625	197	0	150 SX CMT

124

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 11/01/2005 11:00 AM
Plug Co. License No.: 33346 Plug Co. Name: TR SERVICE AND RENTAL, INC.
Proposal Rcvd. from: G P STOEPPELWERTH Company: DARRAH, JOHN JAY, JR. Phone: (620) 786-4046

Proposed Plugging Method: Ordered 300 sxs 60/40 pozmix - 10% gel - 500# hulls.
Junk-tubing and packer at 2821'.
CIBP at 3500'.

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 11/01/2005 3:00 AM KCC Agent: PAT STAAB

Actual Plugging Report:

Log Tech perfed at 1970' and 1160'.
TR Service RIH with tubing to 2775'.
Swift Cementing rigged to tubing and pumped 40 sxs cement neat followed with 60 sxs with 300# hulls mixed in.
Pulled tubing to 2000'. Swift rigged to tubing and pumped 90 sxs cement with 200# hulls mixed in to circulate cement to surface.
Pulled tubing and tied onto 5 1/2" casing with a swedge - pumped 40 sxs.
Max. P.S.I. 400#. S.I.P. 150#.
Rigged up to 8 5/8" casing and pumped 50 sxs.
Max. P.S.I. 200#. S.I.P. 75#.

Perfs:

Top	Bot	Thru	Comments
3634	3817		

Remarks: LEASE ORIGINALLY KNOWN AS MCPHERSON #5. SWIFT CEMENTING SERVICES-TICKET #9219.

Plugged through: TBG

District: 04

Signed *Pat Staab*
(TECHNICIAN)

INVOICED

DATE 11-4-05

INV. NO 2006060700

RECEIVED

NOV 04 2005

KCC WICHITA

Form CP-2/3

NOV 02 2005

PROCESSED

IMPERIAL OIL

#5

McPHERSON

4-9-23W

S2 SE-SW

Contr. HARMS-BURT DR LG

GRAHAM

County

E 2309RB Comm. 3-30-57

Comp. 6-7-57

IP 952 BOPD

Tops	Depth	Datum
HEER	3589	-1280
TOP	3611	-1302
LANS	3627	-1318
TD	3838	-1529

Casing


8" 197

5" 3838

DST 3666-72/2 HR, 1000' GAS,
150' MDY O, 40' MDY WTR, BHP
1380#

DST 3689-98/1 HR, 5' MUD, BHP
0#

PERF 28/3813-17: SWB 3 BOPH/5 HR: ACID 500
 BRUSH CREEK POOL SWB 10 BOPH/8 HR
 ACID 3000: SWB 20
 BOPH/6 HRS: 30/
 3782-86: PLUG 3800
 ACID 4000: SWB 23
 BOPH/8 HRS



INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS