

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-065-02807-00-00
Spot: SESENW Sec/Twnshp/Rge: 9-9S-23W
2970 feet from S Section Line, 2970 feet from E Section Line
Lease Name: BUSH CREEK UNIT Well #: 204
County: GRAHAM Total Vertical Depth: 3910 feet

Operator License No.: 5088
Op Name: DARRAH, JOHN JAY, JR.
Address: 225 NORTH MARKET, STE 300
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3910	0	125 SX CMT
SURF	8.625	212	0	175 SX CMT

08
11/27

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/31/2005 11:00 AM
Plug Co. License No.: 33346 Plug Co. Name: TR SERVICE AND RENTAL, INC.
Proposal Rcvd. from: G P STOEPPELWERTH Company: DARRAH, JOHN JAY, JR. Phone: (620) 786-4046

Proposed Plugging Method: Ordered 250 sxs 60/40 pozmix - 10% gel - 300# hulls - 13 sxs gel.
Squeezed at 1900' - 2359' - 3005'.

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 10/31/2005 3:00 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Log Tech RIH and parted at 1200' and 2035'.
Alliance RIH with tubing to 3200'.
Swift rigged to tubing and pumped 50 sxs 60/40 pozmix with 300# hulls mixed in.
Pulled tubing to 3000' and pumped 13 sxs gel mixing it 9.5 lbs to cover 1000'.
Pulled tubing to 2000' and pumped 100 sxs 60/40 pozmix to circulate cement to surface.
Tied onto 8 5/8" casing and pumped 10 sxs.
Max. P.S.I. 300#. S.I.P. 200#.
Tied back onto 5 1/2" casing and pumped 45 sxs 60/40 pozmix.
Max. P.S.I. 200#. Blew small hole in casing head. Hole was standing full.
11/01/2005 - Topped off with 20 sxs cement

Perfs:

Top	Bot	Thru	Comments
3730	3887		

Remarks: LEASE ORIGINALLY KNOWN AS BIEKER #A-4. SWIFT CEMENTING SERVICES-TICKET #9218.

Plugged through: TBG

District: 04

Signed *Pat Staab*
(TECHNICIAN)

110

INVOICED
DATE 11-4-05
INV NO 2006060700

RECEIVED
NOV 04 2005
KCC WICHITA

NOV 01 2005

