

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-159-21521-00-01
Spot: S2SWNENW Sec/Twnshp/Rge: 19-18S-9W
1140 feet from N Section Line, 1650 feet from W Section Line
Lease Name: BOLDT A Well #: 5
County: RICE Total Vertical Depth: 3222 feet

Operator License No.: 3682
Op Name: CONNELL, MARK ALLEN
Address: 606 W ALBRO
CLAFLIN, KS 67525

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	5.5	3214	1685	140 SX CMT
SURF	8.625	233	0	165 SX CMT

#104 72

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 10/10/2005 10:00 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MIKE KELSO Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: See actual report.

Plugging Proposal Received By: VIRGIL CLOTHIER WitnessType: NONE
Date/Time Plugging Completed: 10/10/2005 2:00 PM KCC Agent: VIRGIL CLOTHIER

Actual Plugging Report:

Sanded open hole to 3160' and capped with 5 sacks of cement. Cut off casing at 1705'. Pulled to 1200' and pumped 35 sacks of cement. Pulled casing to 850' and pumped 35 sacks of cement. Pulled casing to 280' and circulated cement to surface.

60/40 posmix with 4% gel

Allied Cement #22666

Perfs:

Top	Bot	Thru	Comments
3214	3222	OH	

RECEIVED
KCC DISTRICT #2
OCT 20 2005
WICHITA, KS

Remarks:

Plugged through: CSG

District: 02

Signed

Virgil Clothier
(TECHNICIAN)

INVOICED

DATE 11-2-05
INV. NO. 2006060691

RECEIVED
NOV 02 2005
KCC WICHITA