

3 022908

15-001-02033-00-00

To:

API NUMBER CONTROL NO. 20060001-012

STATE CORPORATION COMMISSION

NE,NE,NE 1/4 Sec/Twp/Rge S24-T.26S.-R.17E.

Wichita State Office Bldg. - PLUGGING SECTION

4706 feet from south section line

130 S. Market, Room 2078

344 feet from east section line

Wichita, Kansas 67202

TECHNICIAN'S PLUGGING REPORT

Lease/Well# HAROLD WOLF NO.18

Operator License # 101

County ALLEN

Operator: STATE OF KANSAS Fee Fund

Well Total Depth 825' feet

Name &

Production Pipe: 2" Size Feet 825'

Address

Surface Casing: 6 1/4" Size Feet 20'

AB oil well ☒ Gas Well ☐ SWD Well/ Input Well ☐

D & A

Other well as hereinafter indicated:

Plugging Contractor: KEPLEY WELL SERVICE, LLC

Lic. # 30670

Address: 19245 FORD ROAD, CHANUTE, KANSAS 66720

Company to plug at: Hour: 8:00A.M. Day: 3 Month: 10 2005

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION

Phone: 620-432-2300

Were: THIS WELL CONSISTED OF 2" CASING TO APPROXIMATELY 825' THAT

HAD BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TO
CIRCULATE THE 2" CASING FULL OF CEMENT.

RECEIVED

OCT 24 2005

KCC WICHITA

Plugging Proposal Received by:

CLAYTON P. TITEL

Plugging attended by Agent: All ☒ Part

TECHNICIAN

None

Operations Completed: Hour: 12:00P.M. Day: 3 Month: 10 2005

Actual Plugging Report: 1" PIPE WAS RAN INTO THE 2" CASING TO 825'.

CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM

THE 2" CASING AT SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT

WAS FILLED FROM SURFACE. 30 SACKS OF CEMENT WERE PUMPED INTO

THIS WELL.

Remarks: (GPS SESSION PT. NO.18) (NO API COULD BE LOCATED)

(If additional description is necessary, use BACK of this form.)

I DID observe this plugging.

Signed:


 TECHNICIAN

