

3 022902

15-001-02035-00-00

To:

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

130 S. Market, Room 2078

Wichita, Kansas 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 101Operator: STATE OF KANSAS Fee Fund

Name & _____

Address _____

AB oil well ☒ Gas Well _____ SWD Well/ Input Well _____ D & A _____

Other well as hereinafter indicated: _____

Plugging Contractor: KEPLEY WELL SERVICE, LLC Lic. # 30670Address: 19245 FORD ROAD, CHANUTE, KANSAS 66720Company to plug at: Hour: 8:00A.M. Day: 29 Month: 9 2005Plugging proposal received from: CLAYTON P. TITELCompany Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300Were: THIS WELL CONSISTED OF 2" CASING TO APPROXIMATELY 850' THATHAD BEEN CEMENTED IN AT T.D. ONLY. THE PLUGGING PROPOSAL WAS TOCIRCULATE AS MUCH OF THE WELL AS POSSIBLE FULL OF CEMENT INSIDEAND OUTSIDE THE 2" CASING.Plugging Proposal Received by: CLAYTON P. TITELPlugging attended by Agent: All ☒ Part _____ TECHNICIAN
None _____Operations Completed: Hour: 12:00P.M. Day: 29 Month: 9 2005Actual Plugging Report: 1" PIPE WAS RAN INTO THE 2" CASING TO 850'.CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM THE2" CASING AT SURFACE. THE 1" PIPE WAS REMOVED. 1" PIPE WAS WASHED INTO THE2" AND 10" ANNULUS TO 600'. CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENTCIRCULATED FROM THE 2" AND 10" ANNULUS AT SURFACE. THE 1" PIPE WASREMOVED. DISPLACEMENT WAS FILLED FROM SURFACE. 260 SACKS OF CEMENTWERE PUMPED INTO THIS WELL.Remarks: (GPS SESSION PT. NO.23) (NO API NO. FOUND)(If additional description is necessary, use BACK of this form.)I DID observe this plugging.

Signed:


TECHNICIANRECEIVED
OCT 24 2005
KCC WICHITA