

3 022909

15-001 - 02036.0000

To:

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

130 S. Market, Room 2078

Wichita, Kansas 67202

API NUMBER CONTROL NO. 20060001-018

NE,NE,NE 1/4 Sec/Twp/Rge S24-T.26S.-R.17E.

5291 feet from south section line

310 feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 101

Operator: STATE OF KANSAS Fee Fund

Name & _____

Address _____

AB oil well ☒ Gas Well _____ SWD Well/ Input Well _____

Other well as hereinafter indicated: _____

Plugging Contractor: KEPLEY WELL SERVICE, LLC

Lic. # 30670

Address: 19245 FORD ROAD, CHANUTE, KANSAS 66720

Company to plug at: Hour: 9:00A.M. Day: 7 Month: 10 2005

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300

Were: THIS WELL CONSISTED OF 2" CASING TO APPROXIMATELY 825' THAT

HAD BEEN CEMENTED IN AT T.D. ONLY THE PLUGGING PROPOSAL WAS TO

CIRCULATE AS MUCH OF THE WELL AS POSSIBLE FULL OF CEMENT INSIDE AND

OUTSIDE THE 2" CASING.

Plugging Proposal Received by:

CLAYTON P. TITEL

Plugging attended by Agent: All ☒ Part _____

TECHNICIAN

None _____

Operations Completed: Hour: 5:00P.M. Day: 7 Month: 10 2005

Actual Plugging Report: 1" PIPE WAS RAN INTO THE 2" CASING TO 798'.

CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM

THE 2" CASING AT SURFACE. THE 1" PIPE WAS REMOVED. 1" PIPE WAS RAN

INTO THE 2" AND 12" ANNULUS TO 325'. CEMENT WAS PUMPED INTO THE 1"

PIPE UNTIL CEMENT CIRCULATED FROM THE SURFACE CASING AT SURFACE.

THE 1" PIPE WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE.

301 SACKS OF CEMENT WERE PUMPED INTO THIS WELL.

Remarks: (GPS SESSION PT. NO.26) (NO API COULD BE LOCATED)

(If additional description is necessary, use BACK of this form.)

I DID observe this plugging.

Signed:


 TECHNICIAN

 RECEIVED
 OCT-24 2005
 KCC WICHITA

