

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-179-21142-00-00  
Spot: W2W2NE Sec/Twnshp/Rge: 6-6S-29W  
1320 feet from N Section Line, 2310 feet from E Section Line  
Lease Name: SHAW Well #: 7-6  
County: SHERIDAN Total Vertical Depth: 4190 feet

Operator License No.: 32047  
Op Name: MICA ENERGY CORP.  
Address: P. O. BOX 20707  
OKLAHOMA CITY, OK 73156

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	8.625	253		

#13618

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/26/2005 9:00 AM  
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY  
Proposal Rcvd. from: KEITH VAN PELT Company: MURFIN DRILLING COMPANY Phone: (785) 443-1857

Proposed Plugging Method: Ordered 200 sxs 60/40 pozmix - 6% gel with 1/4# flocele per sack.  
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: ROGER MOSES WitnessType: NONE  
Date/Time Plugging Completed: 10/26/2005 10:30 AM KCC Agent: ROGER MOSES

Actual Plugging Report:

Perfs:

1st. Plug at 2580' w/25 sxs.  
2nd. Plug at 1745' w/100 sxs.  
3rd. Plug at 303' w/40 sxs.  
4th. Plug at 40' w/10 sxs.  
Rathole with 15 sxs.  
Mousehole with 10 sxs.

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: DP

District: 04

Signed Roger A Moses  
(TECHNICIAN)

NOV 03 2005

INVOICED  
DATE 11-4-05  
2006060706

RECEIVED  
NOV 04 2005  
KCC WICHITA