

3 022907

15 - 001.02032.00-00

To:

STATE CORPORATION COMMISSION

Wichita State Office Bldg. - PLUGGING SECTION

130 S. Market, Room 2078

Wichita, Kansas 67202

API NUMBER CONTROL NO. 20060001-011

NE,NE,NE 1/4 Sec/Twp/Rge S24-T.26S.-R.17E.

4891 feet from south section line

420 feet from east section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 101

Operator: STATE OF KANSAS Fee Fund

Name & _____

Address _____

AB oil well ☒ Gas Well _____ SWD Well/ Input Well _____ D & A _____

Other well as hereinafter indicated: _____

Plugging Contractor: KEPLEY WELL SERVICE, LLC Lic. # 30670

Address: 19245 FORD ROAD, CHANUTE, KANSAS 66720

Company to plug at: Hour: 1:30P.M. Day: _____ 3 Month: 10 2005

Plugging proposal received from: CLAYTON P. TITEL

Company Name: KANSAS CORPORATION COMMISSION Phone: 620-432-2300

Were: THIS WELL CONSISTED OF 2" CASING TO APPROXIMATELY 825' THAT
HAD BEEN CEMENTED IN FROM BOTTOM TO TOP. THE PLUGGING PROPOSAL WAS TO
CIRCULATE THE 2" CASING FULL OF CEMENT.

RECEIVED
OCT 24 2005
KCC WICHITA

Plugging Proposal Received by: CLAYTON P. TITEL

Plugging attended by Agent: All ☒ Part _____ TECHNICIAN
None _____

Operations Completed: Hour: 3:30P.M. Day: _____ 3 Month: 10 2005

Actual Plugging Report: 1" PIPE WAS RAN INTO THE 2" CASING TO 800'.

CEMENT WAS PUMPED INTO THE 1" PIPE UNTIL CEMENT CIRCULATED FROM

THE 2" CASING AT SURFACE. THE 1" PIPE WAS REMOVED. DISPLACEMENT

WAS FILLED FROM SURFACE. 53 SACKS OF CEMENT WERE PUMPED INTO

THIS WELL.

Remarks: (GPS SESSION PT. NO.17) (NO API COULD BE LOCATED)

(If additional description is necessary, use BACK of this form.)

I DID observe this plugging.

Signed:

Clayton P. Titel
TECHNICIAN

Bm