

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-031-22120-00-00  
Spot: NESWSWNW Sec/Twnshp/Rge: 12-23S-15E  
2122 feet from N Section Line, 518 feet from W Section Line  
Lease Name: BRILES Well #: 8  
County: COFFEY Total Vertical Depth: 1050 feet

Operator License No.: 8210  
Op Name: BIRK, EDWARD E.  
Address: 302 S. 16TH STREET  
BURLINGTON, KS 66839

String	Size	Depth (ft)	Pulled (ft)	Comment
SURF	7	40		

# 35<sup>00</sup>

Well Type: DH UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 10/18/2005 2:00 PM  
Plug Co. License No.: 31280 Plug Co. Name: BIRK, BRIAN L DBA BIRK PETROLEUM  
Proposal Rcvd. from: EDWARD BIRK Company: BIRK, BRIAN L DBA BIRK PETROL Phone: (620) 364-2745

Proposed Plugging Method: THIS WELL CONSISTED OF AN UNCASED BORE TO 1050'. THE PLUGGING PROPOSAL WAS TO PLACE A 50' CEMENT PLUG AT T.D., A 50' CEMENT PLUG AT 700', AND A CONTINUOUS CEMENT PLUG FROM 250' TO SLURFACE.

Plugging Proposal Received By: CLAYTON TITEL Witness Type: PARTIAL  
Date/Time Plugging Completed: 10/18/2005 6:00 PM KCC Agent: CLAYTON TITEL

Actual Plugging Report:

Perfs:

2" TUBING WAS RAN INTO THE WELL TO T.D.. 10 SACKS OF CEMENT WERE PUMPED THROUGH THE 2" TUBING TO T.D.. THE 2" TUBING WAS PULLED TO 700' AND 10 SACKS OF CEMENT WERE PUMPED TO THAT DEPTH. THE TUBING WAS PULLED TO 250'. CEMENT WAS PUMPED INTO THE 2" TUBING UNTIL CEMENT CIRCULATED FROM THE SURFACE CASING AT SURFACE. THE TUBING WAS REMOVED. DISPLACEMENT WAS FILLED FROM SURFACE.

RECEIVED  
KCC DISTRICT #3

OCT 26 2005

CPT

CHANUTE, KS

Remarks:

Plugged through: TBG

District: 03

Signed

Clayton P. Titel

(TECHNICIAN)

INVOICED  
11-3-05  
2006060696

RECEIVED  
NOV 03 2005  
KCC WICHITA